

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: GENESEE (County), Located In:, Corner Code #/1. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

20119
RECORDED
RECEIVED
APR 4 2 55 PM '95
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked in row 5, column H.

I, RICHARD H. KRAFT, in a field survey on, DECEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1823 - GLO - HARVEY PARKE - DEPUTY SURVEYOR - SET CORNER - NO ACCESSORIES
GCRC - FOUND 1/2" PIPE - 4 ACCESSORIES
MSHD - FOUND 3/4" PIPE - 5 ACCESSORIES
1972 - FOUTZ - FOUND 1" BAR IN MONUMENT BOX - 3 ACCESSORIES
1972 - PIOTROWSKI - FOUND PIPE IN MONUMENT BOX - 2 ACCESSORIES
1979 - S. BROWN - FOUND 3/4" PIPE IN MONUMENT BOX - 3 ACCESSORIES
1980 - P. PANGRES - FOUND 1" IRON - 4 ACCESSORIES
1995 - G. BALLARD - FOUND 1/2" PIPE IN MONUMENT BOX - 5 ACCESSORIES

SURVEY & REMONUMENTATION
MAY 31 2000
SECTION

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1995 GENESEE COUNTY RE-MONUMENTATION PROGRAM
MSHD - FOUND 2 ACCESSORIES
1972 - FOUND 2 ACCESSORIES
1972 - FOUND 2 ACCESSORIES
1979 - FOUND 1 ACCESSORY
1995 - FOUND 3 ACCESSORIES

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. [Signature]
Date 12-20-95

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD GENESEE COUNTY MONUMENT IN MONUMENT BOX
FOUND NAIL & TAG IN POWER POLE - WEST, 61.3 FT.
FOUND NAIL & TAG IN 24" BOX ELDER - N 85° E, 30.0 FT.
TOP-CENTER - GUARDRAIL POST - S 15° E, 75.2 FT.
FOUND ROWE NAIL & TAG IN 18" TREE - S 75° W, 50.31 FT.

Signed by [Signature] Date 12-23-95
Surveyor's Michigan License No. 10064