

RECORDED
McPherson

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GENESEE
(County)

Located In:

Corner Code #/

- 1. Public Land Survey T 6N R 6E K-4
- T R
- T R
- T R
- 2. Property Controlling S T R
- In Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

20121

9:00 Filed & Recd

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, RICHARD H. KRAFT, in a field survey on, DECEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 - 1823 - GLO - HARVEY PARKE, DEPUTY SURVEYOR - SET POST - NO ACCESSORIES
 - 1978 - F. SHALTZ, R.L.S. - FOUND POST - SET IRON - 2 ACCESSORIES
 - 1978 - F. SHALTZ - RECORDED PLAT OF HILL- I-75 INDUSTRIAL SITE - MEASURED SW CORNER PLAT TO W 1/4 - WEST 617.17 FT.
 - 1995 - D. KENNEY - P.S. - FOUND ROWE ENGINEERING IRON - MEASURED EAST 617.17 FT. TO PLAT COR.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - 1995 GENESEE COUNTY RE-MONUMENTATION PROGRAM
 - 1978 - FRED SHALTZ - FOUND WOOD POST - SET IRON - 2 ACCESSORIES
 - 1978 - FRED SHALTZ - MEASURED SW CORNER PLAT HILL - I-75 INDUSTRIAL SITE WEST TO W 1/4-617.17 FT
 - 1995 - D. KENNEY - FOUND ROWE ENGINEERING IRON - MEASURED EAST 617.17' TO PLAT MONUMENT

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. [Signature]
Date 12-20-95

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - SET STANDARD GENESEE COUNTY MONUMENT IN MONUMENT BOX
 - E-W CHAIN LINK FENCE - NORTH 1.0 FT.
 - FOUND NAIL & TAG - E-FACE 30" TREE - S 10° E, 97.90 FT.
 - GAS MARKER POST & SIGN - S 30° W, 76.71 FT.
 - SW CORNER HILL-I-75 INDUSTRIAL SITE PLAT - EAST 616.17 FT.
 - SE CORNER - PREMIERE PACKAGING BUILDING - N 10° W, 136.8 FT.

SURVEY & RE-MONUMENTATION

MAY 31 2000

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 10064

Date 12-23-95