

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>GENESEE</u> (County)	Located in:	Corner Code #1
1. Public Land Survey	T <u>6N</u> R <u>6E</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
REGISTERED
APR 4 2 56 PM '95
GENESEE COUNTY

20122 9.00 Filed & Recd

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, RICHARD H. KRAFT, in a field survey on, DECEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 - GLO - HARVEY PARKE, DUPTY SURVEYOR - SET CORNER - NO ACCESSORIES
- GCRC - FOUND PIPE - 4 ACCESSORIES
- 1979 - J. FOKENS - FOUND 1/4" RE-ROD IN MONUMENT BOX - 3 ACCESSORIES
- 1979 - S. BROWN - FOUND 3/8" IRON PIN IN MONUMENT BOX - 3 ACCESSORIES
- 1995 - R. FRANK - FOUND RE-ROD IN MONUMENT BOX - 4 ACCESSORIES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 GENESEE COUNTY RE-MONUMENTATION PROGRAM

- 1979 - FOUND 2 ACCESSORIES
- 1979 - FOUND 3 ACCESSORIES
- 1995 - FOUND 3 ACCESSORIES

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. [Signature]
Date 12-27-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD GENESEE COUNTY MONUMENT IN MONUMENT BOX
- GC TAG IN 15" HICKORY - SOUTH 63.16 FT.
- CONCRETE MONUMENT - NORTH - 50.1 FT.
- CORNER POST - SOUTH - 35.85 FT.
- FOUND NAIL & TAG IN POWER POLE - N 70° W, 94.9 FT.
- FOUND NAIL & TAG IN POWER POLE - N 5° E, 46.4 FT.

SURVEY & REMONUMENTATION

MAY 31 2008

SECTION

Signed by [Signature] Date 12-29-95
Surveyor's Michigan License No. 10064