

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
REGISTERED
APR 4 2 57 PM '98
M. J. P. M.

For corners in

GENESEE <small>(County)</small>	Located In:	Corner Code =//
1. Public Land Survey	T <u>6N</u> R <u>6E</u>	M-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

20125 9:00 Filed & Recd
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RICHARD H. KRAFT, in a field survey on, DECEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1823 - GLO - HARVEY PARKE - DEPUTY SURVEYOR - SET CORNER - NO ACCESSORIES
 - 1920 - GCRC - FOUND STONE - 4 ACCESSORIES
 - 1970 - GCRC - FOUND TAG IN CENTERLINE OF FENTON ROAD - 4 ACCESSORIES
 - 1972 - C. CARLSON - FOUND IRON - 3 ACCESSORIES
 - 1995 - RICHARD H. KRAFT - FOUND 1" IRON IN MONUMENT BOX

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1995 GENESEE COUNTY RE-MONUMENTATION PROGRAM
- 1823 - GLO MEASURED SE CORNER SECTION 12, T6N, R6E - SOUTH 110.22 FT. TO SW CORNER SECTION 7, T6N, R7E
 - 1920 - GCRC - SAME MEASUREMENT - SOUTH 110.34 FT.
 - 1995 - RICHARD H. KRAFT - SAME MEASUREMENT - SOUTH 110.34 FT.

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlson
Date 12-27-95

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- SET STANDARD GENESEE COUNTY MONUMENT IN MONUMENT BOX
 - SET GC TAG - WOOD POST - N 45° E, 58.3 FT.
 - SET GC TAG IN WOOD POST - N 45° E, 54.0 FT.
 - SET GC TAG IN WOOD POST - S 45° W, 48.6 FT.
 - SET GC TAG IN WOOD POST - WEST - 29.2 FT.
 - MONUMENT BOX - SW CORNER SECTION 7, T6N, R7E - 110.34 FT.

SURVEY & RE-MONUMENTATION
MAY 31 2000
SECTION

Signed by Richard H. Kraft Date 12-29-95
Surveyor's Michigan License No. 10064