

**SURVEY &  
REMONUMENTATION**

MASTER LIBER **3685** PAGE **937** MAR 05 1998

RECORDED  
DEC 29 11 33 AM '97

**1997 REMONUMENTATION PROGRAM SECTION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

|                                       |                         |               |
|---------------------------------------|-------------------------|---------------|
| <u>Genesee</u><br>(County)            | Located In:             | Corner Code # |
| 1. Public Land Survey                 | T <u>6N</u> R <u>7E</u> | <u>C-6</u>    |
|                                       | T ___ R ___             | _____         |
|                                       | T ___ R ___             | _____         |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___       | _____         |
|                                       | S ___ T ___ R ___       | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___       | _____         |
|                                       | S ___ T ___ R ___       | _____         |

GENESEE COUNTY  
REGISTER OF DEEDS  
Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kevin B. Cleaver, in a field survey on December 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

|    |    |   |   |    |   |    |   |    |   |    |   |    |   |
|----|----|---|---|----|---|----|---|----|---|----|---|----|---|
|    | A  | B | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 16 |   |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |   |    |   |    |   |    |   |    |   |    |   |

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1823 GLO Set post and two (2) accessories  
March 21, 1949 GEI Survey for F.C. Jehley  
August 8, 1978 GEI Set 'T' Iron at Base of Steel Fence Post and two (2) accessories

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Carlson  
Date 12-1-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 'T' Iron at base of steel fence post;  
Found distances C-6 to C-5 and C-6 to C-7 from March 21, 1949 GEI records;  
Found two (2) accessories, and distance C-6 to SW Corner of the plat of "Riegler Acres No. 1" from August 8, 1978 GEI records;

This corner was ratified by the Genesee County Peer Review Committee on December 4, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1997, #29242 over a 'T' Iron.

N 85° W, 10.20', Set Genesee County Re-mon. Nail and Tag on the South Face 15" Ash  
North, 13.60', Found GEI Nail and Tag on a 12" Ash  
North, 2.60', Set Genesee County Re-mon. Nail and Tag on the West Face 9" Multi-stem Ash  
N 75° E, 21.82', Set Genesee County Re-mon. Nail and Tag on the South Face 8" Tree  
S 85° E, 1.12', West Face 4" Metal Post for the West end of Gate of a 6' C.L.F. for Bicentennial Park

Signed by Kevin Banfield Cleaver  
Kevin Banfield Cleaver, P.S.  
Field Manager



Date 12/24/97

Surveyor's Michigan License No. 29242

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983 REVISED OCT., 1995