

SURVEY & REMONUMENTATION

RECORDED

REGISTERED

MAR 05 1998

DEC 29 11 33 AM '97

MASTER LIBER 3685 PAGE 936

SECTION

GENESEE COUNTY REGISTERED

1997 REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Genesee (County)

Located In: Corner Code #

1. Public Land Survey

T 6N R 7E C-7

2. Property Controlling in Section

T R

3. Miscellaneous Property in Sec.

T R

S T R

S T R

4. Lot No. Recorded Plat

5. Private Claims

I, Kevin B. Cleaver, in a field survey on December 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO Set post and two (2) accessories
March 21, 1949 GEI Records, Survey for F.C. Jehley
No Date GEI Iron in Pavement, three (3) accessories
No Date GEI Material Not Specified, five (5) accessories
Feb. 11, 1975 GCRC LCRC, L 2125, P 133, Boat Spike in Mon. Box, three (3) accessories
1960 MDOT File No. 25-R-2, Route I-75, Sheet No. 3
Feb. 11, 1975 LCRC Certified Survey, L 1909, P 834, Found Boat Spike in Mon. Box same three (3) accessories as 1975
Feb. 11, 1975 GEI Boat Spike in Monument Box, five (5) accessories
Nov. 21, 1994 GEI Found Boat Spike in Monument Box, five (5) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Boat Spike in Monument Box

Found dist. C-7 to C-6 from 3-21-49 GEI survey; Found one (1) accessory from LCRC L 2125 P 133; Found dist. C-7 to S.B. Lane from 1960 MDOT; Found one (1) accessory from survey L 1909 P 834; Found three (3) accessories from 2-11-75 GEI records; Found five (5) accessories from 11-21-94 GEI records.

Corner was ratified by the Genesee County Peer review committee on December 4, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1997, #29242 over a Boat Spike in a Monument Box.

- S 30° E, 25.54' - Found Nail and Tag #12024 on Guard Post
S 55° W, 30.54' - Set Nail and Tag Re-mon. on Guard Post
N 40° E, 25.14' - Set Nail and Tag Re-mon. on Guard Post
S 25° W, 54.00' - Found Nail and Tag on East Face Power Pole

Signed by Kevin Banfield Cleaver, P.S., Field Manager

Date 12/24/97

Surveyor's Michigan License No: 29242



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983 REVISED OCT., 1985

Grid table with columns A-M and rows 1-13. A dot is marked at row 7, column C.

Ratified by Peer Group In accordance with P.A. 345, 1990

Co. Rep. Carl Carlson

Date 12-4-97