

DEC 29 11 33 AM '97

MAR 05 1998

SECTION

1997 REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

GENESEE COUNTY

For corners in

<u>Genesee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 7E	D-5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kevin B. Cleaver, in a field survey on December 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO Set post and two (2) accessories
- Jan. 21, 1963 GEI Survey for Grand Blanc Schools
- Oct. 31, 1973 GCRD LCRC, Liber 1875, Page 592, Found 1/2" Bar, four (4) accessories
- Oct. 31, 1973 GCRD Certified Survey, Liber 1872, Page 366,
- Oct. 11, 1974 GCRD Recorded plat of "Porter Meadow"
- May 17, 1989 GEI Survey for New Life Christian Fellowship Church
- Jan. 13, 1995 GEI Re-rod in Monument Box, four (4) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Re-Rod in Monument Box

Found distance D-5 to C-5 from January 21, 1963 GEI survey; Found three (3) accessories from October 31, 1973 LCRC L 1875 P 592; Found distance D-5 to C-5 from October 31, 1973 survey L 1872 P 366; Found plat monumentation in the recorded plat of "Porter Meadow" L 53 P 40 and 41 from October 11, 1974 survey; Found distances D-5 to C-5 and D-5 to D-4 and angle C-5, D-5, D-4 from May 17, 1989 GEI survey; Found four (4) accessories from January 13, 1995 GEI survey.

The monument found was ratified by the Genesee County Peer review committee on December 4, 1997, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1997, #29242 in concrete over a re-rod in a monument box.

- N 50° W, 92.97' - Found Nail and Tag in the Southwest face of a power pole
- S 45° W, 112.47' - Set Nail and Genesee County Witness Tag in the Southeast face power pole
- S 45° E, 64.58' - Found Nail and Tag in the South face 18" Apple
- N 45° E, 49.11 - Found 'X' on the North rim sanitary manhole

Signed by Kevin Banfield Cleaver
 Kevin Banfield Cleaver P.S.,
 Field Manager

Date 12/24/97

Surveyor's Michigan License No. 29242



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983 REVISED OCT., 1995

97H-GCRM-LCRC-3603

88570

Register of Deeds Stamp & File Number

900 filed

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Ratified by Peer Group In
 accordance with P.A. 345, 1990

Co. Rep. Carl Carlson
 Date 12-4-97