

SURVEY & REMONUMENTATION

MAR 23 2000

MASTER LIBER 4355 PAGE 119

SECTION

**1999 GENESEE COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Genesee (County)	Located In: Grand Blanc	Corner Code #
1. Public Land Survey	T6N R7E	D-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Dec 21 3 10 PM '99
109087
Register of Deeds Stamp & File Number
Filed, Rec 9.00

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kevin B. Cleaver, in a field survey on December 9, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1815 General Land Office (GLO) field notes: set post w/two accessories
- Undated Cornerstone Surveying and Engineering witness ties: rail road spike w/one accessory
- 8/29/72 Land Corner Recordation Certificate (LCRC), Liber 1838, Page 153: rail road spike w/two accessories
- 8/29/72 P.A. 132 Certificate Survey, Liber 1840, Pages 638-639: rail road spike w/ two accessories and half-mile measurement
- 1999 Wade-Trim, Inc. field notes: closing corner measurement and measurement to section corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- GLO corner and accessories not found
- Recovered corner and one accessory from undated witness ties
- Recovered corner from 1972 LCRC
- Recovered corner and confirmed within acceptable tolerance half-mile measurement from 1972 certified survey
- Confirmed closing corner measurement and measurement to section corner from 1999 field notes

This monument found was ratified by the Genesee County Remonumentation Peer Review Committee on December 1, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set in concrete the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1999, #29242" over rail road spike at the base of a 9" diameter concrete post.

- N 80° W 102.00' set Genesee County witness tag in south face of 30" oak
- N 31° W 34.91' set Genesee County witness tag in northeast face 18" shagbark hickory
- North 43.19' set Genesee County witness tag in west face of 4" ash
- N 25° E 91.59' set Genesee County witness tag in northwest face of 7" ash
- S 89° E 5.05' Rowe Inc. Trav. rod

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlson
Date 12-1-99

Signed by Kevin B. Cleaver
Surveyor's Michigan License No. 29242

Date 12/20/99

