

**SURVEY & REMONUMENTATION**

MAR 05 1998 MASTER LIBER 3685 PAGE 934

RECORDED  
REGISTERED  
DEC 29 11 33 AM '97

**SECTION 1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Genesee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>7E</u>	<u>E-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

GENESEE COUNTY  
*Good find & rec*  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kevin B. Cleaver, in a field survey on December 1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO Set post and two (2) accessories
- April 30, 1941 CPCo Found Consumer Power Monument
- 1968 GEI Found Consumers Power Company Pipe, five (5) accessories
- Oct. 15, 1993 GEI Found Consumers Power Company Monument, 2" Pipe in Concrete, five (5) accessories

Ratified by Peer Group in accordance with P.A. 345, 1990  
Co. Rep. Carl Carlson  
Date 12-4-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" Pipe in Concrete Consumers Power Company Monument

Found distances E-4 to E-5 and E-4 to E-3 and angle E-3, E-4, E-5 from April 30, 1941 C.P.Co. records; Found three (3) accessories from 1968 GEI records; Found three (3) accessories from October 15, 1993 GEI records.

The monument found was ratified by the Genesee County Peer Review Committee on December 4, 1997, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Consumer Power Company galvanized steel monument.

- N 08° W, 70.17' - Found MSHD Tag in the West face of a power pole
- N 80° W, 26.41' - Found Nail and Tag in the South face of a 10" poplar
- S 75° E, 102.22' - Northwest Corner 6' C.L.F.
- S 30° W, 82.41' - Set Genesee County witness nail and tag in the Northwest face of a power pole

Signed by Kevin Banfield Cleaver  
Kevin Banfield Cleaver, P.S.,  
Field Manager

Date 12/24/97

Surveyor's Michigan License No. 29242



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983 REVISED OCT., 1995