

SURVEY & REMONUMENTATION

MAR 05 1998

MASTER LIBER 3685 PAGE 933

RECORDED
 REGISTERED
 Dec 29 11 33 AM '97

SECTION

**1997 REMONUMENTATION PROGRAM
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970**

GENESEE COUNTY

For corners in

<u>Genesee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 7E	E-5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

900 filed & rec

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	15		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kevin B. Cleaver, in a field survey on December 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Ratified by Peer Group in accordance with P.A. 345, 1990
 Co. Rep. Carl Carlson
 Date 12-4-97

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO Set post, and two (2) accessories
- April 30, 1941 C.P.Co Consumer Power Iron
- 1968 GEI Consumers Power Iron in Concrete, three (3) accessories
- Nov. 9, 1992 GCRD Certified Survey, L 2479, P 432 - Found C.P.Co. 'T' Iron, four (4) accessories
- Dec. 22, 1992 GCRD LCRC, L 2483 P 631 - Found 'T' Iron Next to 2" Pipe, four (4) accessories
- May 16, 1995 GCRD Certified Survey, L 2575, P 496 - Found 'T' Iron, four (4) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 'T' Iron
 Found distance E-5 to E-4 and angle E-3, E-4, E-5 from April 30, 1941 C.P.Co. records; Found one (1) accessory from 1968; Found distance E-5 to E-6 and four (4) accessories from November 9, 1992 survey L 2479 P 432; Found four (4) accessories from December 22, 1992 LCRC L 2483 P 631; Found distance E-5 to E-6 and four (4) accessories from May 16, 1995 survey L 2575 P 496.

The monument found was ratified by the Genesee County Peer Review Committee on December 4, 1997, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1997, #29242 over 'T' Iron.

- S 10° E, 56.74' - Found Nail and Tag in the East face of an 8" Maple
- S 10° W, 60.98' - Found Nail and Tag in the East face of a 12" Maple
- S 50° W, 61.00' - Found Nail and Tag in the North face of a 15" Maple
- West, 14.25' - Found Nail and Tag in the South face of a 12" Tree

Signed by Kevin Banfield
 Kevin Banfield Cleaver, P.S.,
 Field Manager



Date 12/24/97

Surveyor's Michigan License No. 29242

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983 REVISED OCT., 1995