

MAR 05 1998

RECORDED

Dec 29 11 33 AM '97

1997 REMONUMENTATION PROGRAM SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Genesee (County), Located In: (T 6N R 7E), Corner Code # (E-6). Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

GENESEE COUNTY REGISTER

90 filed & rec Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at row 6, column D.

I, Kevin B. Cleaver, in a field survey on December 3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO Set post and two (2) accessories
Feb. 3, 1937 GCRD Recorded Plat of "Grand Blanc Acres" L18 P 32 and 33
Oct. 17, 1957 GCRD Recorded Plat of "Green Valley Subdivision No. 3" L 33 P 3
1968 GEI 3/4" Pipe, four (4) accessories
June 24, 1992 GCRD Certified Survey, L 2465, P 531 and 532 - Found 1/2" Re-rod in Pipe, four (4) accessories
Nov. 9, 1992 GCRD Certified Survey, L 2479, P 432 - Found 1/2" Re-rod in Pipe, four (4) accessories
Dec. 22, 1992 GCRD LCRC, L 2483 P 631 - Found Re-rod in Pipe, four (4) accessories
Jan. 30, 1995 GEI Survey for Auker Homes - Found Re-rod in Pipe, four (4) accessories
May 19, 1995 GCRD Certified Survey, L 2575, P 496 - Found 1/2" Re-rod in Pipe, four (4) accessories
Sept. 5, 1996 GCRD Certified Survey, L 3371, P 234 and 235 - Found 1/2" Re-rod in Pipe, four (4) accessories
Sept. 13, 1996 GCRD Certified Survey, L 3377, P 655 - Found 1/2" Re-rod in Pipe, four (4) accessories

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl Carlson Date 12-4-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rod in Pipe

Found distance E-6 to F-6 and plat monumentation in the recorded plat of "Grand Blanc Acres" L 18 P 32 - 33 February 3, 1937; Found distance E-6 to E-7 and plat monumentation in the recorded plat of "Green Valley Subdivision No. 3" L 33 P 3 October 17, 1957; Found two (2) accessories from 1968 GEI records; Found distance E-6 to E-5 and four (4) accessories from June 24, 1992 survey L 2465 P 531 - 532; Found distance E-6 to E-5 and four (4) accessories from November 9, 1992 survey L 2479 P 432; Found four (4) accessories from December 22, 1992 LCRC L 2483 P 631; Found five (5) accessories from January 30, 1995 GEI survey; Found distances E-6 to E-5 and four (4) accessories from May 19, 1995 survey L 2575 P 496, September 5, 1996 survey L 3371 P 234 - 235 and September 13, 1996 survey L 3377 P 655. The monument found was ratified by the Genesee County Peer Review Committee on December 4, 1997, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set the standard Bernsten monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1997, #29242 over 1/2" Re-rod in pipe.

- East, 12.69' - Found Nail and Tag in the North face of an 8" Oak
S 50° E, 18.57' - Found Nail and Tag in the Northeast face of a 6" Oak
S 30° W, 20.71' - Found Nail and Tag in the Southeast face of a Hickory
West, 30.30' - Found Nail and Tag in the North face of an 18" Oak

Signed by Kevin Banfield Cleaver, P.S. Field Manager

Date 12/24/97

Surveyor's Michigan License No. 29242



APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983 REVISED OCT., 1995