

**SURVEY & REMONUMENTATION**

**MAR 23 2000**

**SECTION**

**1999 GENESEE COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MASTER LIBER 4355 PAGE 117

For corners in

Genesee (County)	Located In: Grand Blanc	Corner Code #
1. Public Land Survey	T6N R7E	E-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

DEC 21 3 10 PM '99  
109085  
Filed & Rec 9-00  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kevin B. Cleaver, in a field survey on December 8, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	16			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1815 General Land Office (GLO) field notes: set post w/two accessories
- 1823 GLO field notes: measurement to closing corner
- Undated Cornerstone Surveying and Engineering survey: pipe w/four accessories
- 3/8/73 Gould Engineering, Inc. (GEI) records: pipe w/three accessories
- 4/2/79 P.A. 132 Certified Survey, Unrecorded: pipe w/two accessories, closing corner measurement, and measurement to section corner
- 5/26/92 P.A. 132 Certified Survey, Liber 2462, Page 476: re-rod w/four accessories and measurements to section corner
- 10/1/92 P.A. 132 Certified Survey, Unrecorded: pipe and closing corner measurement
- 7/30/98 Wade Trim field notes: closing corner measurement

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

GLO corner and accessories not found  
Confirmed within acceptable tolerance 1823 closing corner measurement  
Recovered corner and four accessories from undated survey  
Recovered corner and three accessories from 1973 records  
Recovered corner, one accessory, and confirmed closing corner measurement and measurements to section corner from 1979 certified survey  
Recovered corner, three accessories, and confirmed closing corner measurement and measurements to section corner from 1992 certified survey  
Recovered corner and confirmed closing corner measurement from 10/1/92 certified survey  
Confirmed closing corner measurement from 1998 field notes  
This monument found was ratified by the Genesee County Remonumentation Peer Review Committee on December 1, 1999.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1999, #29242" 6" below surface over 1.2' long 1" diameter pipe

S 30° W 26.15' set Genesee County witness tag in west face 24" twin oak  
N 31° E 20.44' set Genesee County witness tag in northwest face 24" oak  
N 13° E 32.85' Delta Surveying and Engineering red  
S 28° E 40.02' 2" diameter pipe with Consumers Power cap  
S 85° E 22.46' Oakland County remonumentation corner with 2" brass cap.

**Ratified by Peer Group in accordance with P.A. 345, 1990**  
Co. Rep. Carl Carlson  
Date 12-1-99

Signed by Kevin B. Cleaver  
Surveyor's Michigan License No. \_\_\_\_\_

Date 12/20/99

