

**SURVEY & REMONUMENTATION**

MAR 23 2000

MASTER LIBER 4355 PAGE 12

SECTION

**1999 GENESEE COUNTY REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Genesee (County)	Located In: Grand Blanc	Corner Code #
1. Public Land Survey	T6N R7E	F-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

GENESEE COUNTY  
REGISTER OF DEEDS  
DEC 21 3 10 PM '99  
109089  
*Filed & Rec 9:00*  
Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kevin B. Cleaver, in a field survey on December 9, 19 99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1815 General Land Office (GLO) field notes: set post w/two accessories
- 7/26/79 Gould Engineering, Inc. (GEI) records: closing corner measurement
- 10/30/79 GEI records: pipe w/ five accessories and closing corner measurement
- 1979 GEI records: pipe, closing corner measurement, and half-mile measurement
- 12/6/91 P.A. 132 Certified Survey, Unrecorded: re-rod and closing corner measurement
- 2/2/97 P.A. 132 Certified Survey, Unrecorded: pipe, closing corner measurement, and half-mile measurement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- GLO corner and accessories not found
- Confirmed closing corner measurement to pipe from 7/26/79 GEI records
- Recovered corner, four accessories, and confirmed closing corner measurement from 10/30/79 GEI records
- Recovered corner and confirmed closing corner and half-mile measurements from 1979 GEI records
- Recovered corner (re-rod) and confirmed closing corner measurement from 1991 certified survey
- Recovered corner and confirmed closing corner and half-mile measurements from 1997 certified survey

This monument found was ratified by the Genesee County Remonumentation Peer Review Committee on December 1, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1999, #29242" over 2.15' long 3/4" pipe with brick shards 7" below surface.

- N 04° E 50.83' set Genesee County witness tag in east face power pole
- N 86° E 19.58' set Genesee County witness tag in north face 8" hickory
- N 72° W 48.35' set Genesee County witness tag in south face 15" twin oak
- S 12° W 47.43' Oakland County witness tag in west face 32" deciduous tree
- N 85° W 6.23' 2" brass cap Oakland County remonumentation corner 4" below surface

**Ratified by Peer Group in  
accordance with P.A. 345, 1990**  
Co. Rep. Carl Carlson  
Date 12-1-99

Signed by Kevin B. Cleaver  
Surveyor's Michigan License No. \_\_\_\_\_

Date 12/29/99

