

SURVEY & REMONUMENTATION

MASTER LIBER **3685** PAGE **927**

MAR 05 1998

RECORDED
[Signature]
REGISTERED
Dec 29 11 32 AM '97

**SECTION 1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Genesee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>7E</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

GENESEE COUNTY REGISTERED OFFICE

900
filed & rec
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kevin B. Cleaver, in a field survey on December 8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO Set post and two (2) accessories
- March 6, 1943 GCRD Recorded Plat of "Assessor's Plat No. 1" L 17, P 53, 54 and 55 - Found Bent Pipe
- Aug. 25, 1986 GCRD LCRC, L 2268 P 592 - Found 3/4" Pipe, four (4) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Pipe

Found plat monumentation in the recorded plat of "Assessor's Plat No. 1" L 17 P 53 - 55 March 6, 1943;
Found four (4) accessories from August 25, 1986 LCRC L 2268 P 591.

The monument found was ratified by the Genesee County Peer Review Committee on December 11, 1997, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1997, #29242 over 3/4" pipe.

- N 75° W, 33.12' - Set Re-mon. Nail and Tag in the South face of a 10" Hickory
- N 5° W, 42.52' - Set Re-mon Nail and Tag in the West face of a light pole
- N 30° E, 3.03' - Set Re-mon. Nail and Tag in the West face of a wood fence post
- S 10° E, 11.84' - Set Re-mon. Nail and Tag in the West face of a wood fence post

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. [Signature]
Date 12-11-97

Signed by Kevin Banfield Cleaver
Kevin Banfield Cleaver, P.S.,
Field Manager



Date 12/24/97

Surveyor's Michigan License No. 29242

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983 REVISED OCT., 1995