

SURVEY & REMONUMENTATION

MAR 05 1998

MASTER LIBER 3685 PAGE 945

RECORDED
REGISTERED
DEC 29 11 33 AM '97

SECTION

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Genesee (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 7E	H-5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

GENESEE COUNTY REGISTERED DEEDS
900 filed
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kevin B. Cleaver, in a field survey on December 15, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO Set post and two (2) accessories
- Aug. 7, 1961 GCRD Recorded plat of "Indian Hill Colony No. 2" L 36 P 46 and 47
- Jan. 23, 1962 GCRD Recorded plat of "Indian Hill Colony No. 3" L 37 P 23 and 24
- Aug. 28, 1986 GCRD LCRC; L 2268 P 593 - Found 'T' Iron with Gould Cap, four (4) accessories
- Feb. 19, 1997 GCRD LCRC, L 3470 P 103 - Set 'T' Iron with Cap #29242, four (4) accessories
- April 9, 1997 GCRD Certified Survey, L 3491, P 887, 888 and 889 - Set 'T' Iron, four (4) accessories

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlson
Date 12-18-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 'T' Iron with Cap #29242

Found distances H-5 between G-5 to I-5 from 1823 GLO records; Found plat monumentation in the recorded plat of "Indian Hill Colony No. 2" L 36 P 46 - 47 August 7, 1961; Found plat monumentation in the recorded plat of "Indian Hill Colony No. 3" L 37 P 23 - 24 January 23, 1962; Found four (4) accessories from August 28, 1986 LCRC L 2268 P 593; Found four (4) accessories from February 19, 1997 LCRC L 3470 P 103; Found four (4) accessories, distanced H-5 to H-4 and H-5 to I-4, and angle H-5, I-5, I-6 from April 9, 1997 survey L 3491 P 887 - 889.

The monument found was ratified by the Genesee County Peer Review Committee on December 18, 1997, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1997, #29242 over a 'T' Iron and large stone.

- East, 20.00' - Found Nail and Tag in the South face of a 21" hickory
- S 30° W, 12.00' - Found Nail and Tag in the Northwest face of a 15 oak
- North, 22.64' - Found Nail and Tag in the East face of an 18" hickory
- N 30° E, 16.65' - Found Nail and Tag in the Northwest face of a 12" oak

Signed by Kevin Banfield Cleaver
Kevin Banfield Cleaver, P.S.
Field Manager

Date 12/24/97



Surveyor's Michigan License No. 29242

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1974