

MAR 23 2000

1999 GENESEE COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Genesee (County)	Located In: Grand Blanc	Corner Code #
1. Public Land Survey	T6N R7E	H-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

GENESEE COUNTY REGISTER OF DEEDS
DEC 21 3 10 PM '99
109891
Filed Rec 9.u
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kevin B. Cleaver, in a field survey on December 9, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1815 General Land Office (GLO) field notes: set post w/two accessories
- 4/4/91 P.A. 132 Certified Survey, Unrecorded: half-mile measurements
- 5/13/96 Tax Roll Parcel #12-34-400-03: measurement to section corner
- 1998 Wade Trim, Inc. field notes: Holly Township half-mile measurement

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

GLO corner and accessories not found
Confirmed within acceptable tolerance 1991 half-mile measurements to J-13. Unable to confirm half-mile measurement to I-13 due to corner being in "Slack Lake"
Unable to recover corner and confirm measurements to section corner
Confirmed within acceptable tolerance 1998 Holly Township half-mile measurement

Monument set on line between the southwest corner of Section 34 (G-13) and the south 1/4 corner of Section 35 (J-13) at a distance of 2653.12' from G-13.
This monument found was ratified by the Genesee County Remonumentation Peer Review Committee on December 1, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1999, #29242".

- N 13° W 39.17' set Genesee County witness tag in east face 12" oak
- N 53° E 54.50' set Genesee County witness tag in southeast face 16" ash
- S 60° E 40.62' set Genesee County witness tag in southeast face 30" oak
- S 40° W 22.56' set Genesee County witness tag in northwest face 17" oak
- N 83° W 16.00' set Genesee County witness tag in north face 20" oak

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlson
Date 12-1-99

Signed by Kevin B. Cleaver
Surveyor's Michigan License No. 29242

Date 12/20/99

