

RECORDED
 REGISTERED
 DEC 29 11 32 AM '97

**1997 REMONUMENTATION PROGRAM
 LAND CORNER RECORDATION CERTIFICATE**
 Filing Requirement of Act 74, Mich. P.A. 1970

GENESEE COUNTY
 REGISTER OF DEEDS

For corners in

<u>Genesee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>7E</u>	<u>1-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

900 filed & rec
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kevin B. Cleaver, in a field survey on December 8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO Set post and two (2) accessories
- Dec. 19, 1963 Recorded Plat of "Bella Vista Estates No. 1" L 39 P 31 and 32
- Jan. 2, 1991 LCRC, L 2448 P 742 - Found 'T' Iron #9431, four (4) accessories
- Dec. 17, 1993 GCRD LCRC, L 2520 P 754 - Found 'T' Iron #9431, four (4) accessories
- Feb. 3, 1994 Certified Survey, L 2524, P 749 - 753 - Found 'T' Iron #9431, four (4) accessories
- Feb. 24, 1995 GCRD Recorded plat of "KirkrIDGE Estates No. 4" L 69 P 15 and 16
- LCRC, L 2448, P 742 - Found 'T' Iron #9431, four (4) accessories
- Aug. 11, 1995 GCRD Recorded Plat of "KirkrIDGE Estates No. 5" L 70 P 12 and 13
- LCRD, L 2448, P 742 - Found 'T' Iron #9431, four (4) accessories
- April 9, 1997 GCRD Certified Survey, L 3491, P 887, 888 and 889

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 'T' Iron

Found plat monumentation in the recorded plat of "Bella Vista Estates No. 1" L 39 P 31 - 32 December 19, 1963; Found four (4) accessories from January 2, 1991 LCRC L 2448 P 742; Found four (4) accessories from December 17, 1993 LCRC L 2520 P 754; Found four (4) accessories and distance 1-6 to 1-5 from February 3, 1994 survey L 2524 P 749 - 753; Found four (4) accessories and plat monumentation from the recorded plat of "KirkrIDGE Estates No. 4" L 69 P 15 - 16 February 24, 1995; Found four (4) accessories and plat monumentation from the recorded plat of "KirkrIDGE Estates No. 5" L 70 P 12 - 13 August 11, 1995; Found distance 1-5 to 1-6 from April 9, 1997 survey L 3491 P 887 - 889.

The monument found was ratified by the Genesee County Peer Review Committee on December 11, 1997, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1997, #29242 over a 'T' Iron.

- N 45° E, 4.43' - Found Nail and Tag in the Northwest face of a 6" tree
- N 10° E, 27.36' - Found Nail and Tag in the West face of a 5" tree
- South, 3.39' - Found North face of C.L.F. post
- East, 35.81' - Found Nail and Tag in a 12" tree

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Paul Cash

Date 12-11-97

Date 12/24/97

Signed by Kevin Banfield Cleaver, P.S.
 Field Manager



Surveyor's Michigan License No. 29242

APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983 REVISED OCT., 1995