

MAR 05 1998

RECORDED REGISTERED DEC 29 11 32 AM '97

SECTION 1997 REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Genesee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>7E</u>	<u>L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

GENESEE COUNTY REGISTERED DEEDS

900 filed & rec
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Kevin B. Cleaver, in a field survey on November 10, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1823 GLO Set post and two (2) accessories
- Dec. 29, 1966 CPCo Found survey monumentation
- 1970± GEI Found concrete monument in East Edge of Fence Line
- Nov. 21, 1979 GCRD Recorded Plat of "Stockbridge Commons" L 58 P 39 and 40 - Concrete Monument
- March 22, 1990 GCRD Certified survey, L 2387 P 904 - Found concrete monument, three (3) accessories
- March 13, 1997 GCRD Certified Survey, L 3497 P 804 - Found concrete monument, four (4) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found concrete monument

Found distances L-3 to K-3 and L-3 along the North and South ¼ Line to North Line C.P.Co. property from December 29, 1966 C.P.Co. records; Found concrete monument in the east edge of the fence line; Found plat monumentation in the recorded plat of "Stockbridge Commons" L 58 P 39 - 40 November 21, 1979; Found three (3) accessories from March 22, 1990 survey L 2387 P 904; Found four (4) accessories from March 13, 1997 survey L 3497 P 804.

The monument found was ratified by the Genesee County Peer Review Committee on November 13, 1997, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found concrete monument

- N 45° E, 0.55' - Found SW face 2" fence post
- S 45° W, 27.43' - Found SE face corner concrete foundation
- S 45° E, 2.98' - Found NW corner concrete pad
- S 60° E, 30.33' - Found NW face 2" fence post

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Paul Carlson
Date 11-13-97

Signed by Kevin Banfield Cleaver
Kevin Banfield Cleaver, P.S.,
Field Manager



Date 12/24/97

Surveyor's Michigan License No. 29242

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971