

**SURVEY &
REMONUMENTATION**

MAR 28 2000

SECTION

**1999 GENESEE COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

MASTER LIBER 4355 PAGE 125

For corners in

<u>Genesee</u> (County)	Located In: Grand Blanc	Corner Code # L-13
1. Public Land Survey	T6N R7E	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

GENESEE COUNTY REGISTER OF DEEDS

DEC 21 3 10 PM '99

10909

Filed & Rec 9:00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **Kevin B. Cleaver**, in a field survey on **December 2, 1999**, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1815 General Land Office (GLO) fieldnotes: set post
- Undated Gould Engineering, Inc. (GEI) records: 'T'-iron in center of anchor post
- 9/7/73 P.A. 132 Certified Survey, Unrecorded: closing corner and half-mile measurements
- 10/73 Land Corner Recordation Certificate (LCRC), Liber 6203, Page 431: closing corner and half-mile measurements
- 10/23/73 LCRC, Liber 1872, Page 827: 'T'-iron w/three accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- GLO corner not found
- Recovered corner from undated GEI records
- Confirmed closing corner and half-mile measurements from 1973 certified survey
- Confirmed closing corner and half-mile measurements from 1973 LCRC
- Recovered corner and three accessories from 10/23/73 LCRC

This monument found was ratified by the Genesee County Remonumentation Peer Review Committee on December 1, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1999, #29242 on top of concrete monument.

- North 16.65' set Genesee County witness tag in east face of 14" ash
- N 40° E 36.71' set Genesee County witness tag in southeast face 11" ash
- S 05° W 18.76' set Genesee County witness tag in west face of 9" ash
- S 55° W 7.05' set Genesee County witness tag in southeast face 6" ash
- N 85° W 35.45' concrete monument with Oakland County Remonumentation brass cap, PS #33136 (L-1).

Signed by *Kevin B. Cleaver*
Surveyor's Michigan License No. _____

Date *12/29/99*



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. *Carl Carlson*
Date *12-1-99*