

**SURVEY &
REMONUMENTATION**

MASTER LIBER 4355 PAGE 126

MAR 23 2000

**1999 GENESEE COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

Genesee (County)	Located In: Grand Blanc	Corner Code #
1. Public Land Survey	T6N R7E	M-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

GENESEE COUNTY
REGISTER OF DEEDS
DEC 21 3 10 PM '99
109094
Filed & Rec 9:00
Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kevin B. Cleaver, in a field survey on December 2, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1815 General Land Office (GLO) fieldnotes: set post w/two accessories
 - Undated Gould Engineering, Inc. (GEI) records: pipe w/four accessories
 - 7/16/62 Oakland County Road Commission (OCRC) records: stone with four accessories
 - 11/71 GEI survey: half-mile measurement
 - 10/73 Land Corner Recordation Certificate (LCRC), Liber 6203, Page 431: half-mile measurements
 - 10/23/73 LCRC, Liber 6203, Page 430: pipe w/five accessories
 - 10/23/73 LCRC, Liber 1872, Page 827: pipe w/five accessories
 - 2/26/74 LCRC, Liber 1881, Page 888: pipe w/five accessories
 - 9/3/97 GEI records: pipe w/four accessories
 - 9/22/97 GEI ALTA survey: half-mile measurement

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- GLO corner and accessories not found
 - Recovered corner and two accessories from undated GEI records
 - Recovered corner and three accessories from 1962 OCRC records
 - Confirmed within acceptable tolerance 1971 GEI half-mile measurement
 - Confirmed within acceptable tolerance 1973 LCRC half-mile measurements
 - Recovered corner and three accessories from 10/23/73 LCRC
 - Recovered corner and three accessories from 10/23/73 LCRC
 - Recovered corner and three accessories from 1974 LCRC
 - Recovered corner and two accessories from 1997 GEI records
 - Confirmed half-mile measurement from 1997 GEI ALTA survey

**Ratified by Peer Group in
accordance with P.A. 345, 1990**
Co. Rep. Carl Carlson
Date 12-1-99

This monument was ratified by the Genesee County Remonumentation Peer Review Committee on December 1, 1999.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Found 2" brass cap stamped "Oakland County Remonumentation P.S. #33136" four inches below gravel surface.
 - S 85° E 20.01' 2" brass tag "Oak. Co. Remon PS #33136" in north face of 10" poplar
 - S 39° E 25.64' 2" brass tag "Oak. Co. Remon PS #33136" in southwest face of 28" oak
 - N 87° W 22.64' 2" brass tag "Oak. Co. Remon PS #33136" in north face of 8" oak
 - N 26° W 53.91' 2" brass tag "Oak. Co. Remon PS #33136" in east face of power pole

Signed by Kevin B. Cleaver
Surveyor's Michigan License No. _____

Date 12/20/99

