

**SURVEY &  
REMONUMENTATION**

MAR 05 1998

MASTER LIBER 3644 PAGE 687



**SECTION  
1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**  
Meeting Requirement of Act 74, Mich. P.A. 1970

For corners in

Genesee Located In: Atlas Corner Code # D-3  
(County)

RECORDED  
RECORD  
06-30 3 37 PM '97  
GENESEE COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey      T 6N    R 8E    D-3  
   T        R  
   T        R  
   T        R
- 2. Property Controlling S    T    R  
    In Section            S    T    R
- 3. Miscellaneous        S    T    R    Ratified by Peer Group in  
    Property in Sec.      S    T    R    accordance with P.A. 345, 1990

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_ Co. Rep. Cad. [Signature]  
5. Private Claims \_\_\_\_\_ Date 9-11-97

I, Gilbert G. Bonno, P.S., in a field survey on August 6, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 1823, GLO J. Wampler DS, set post and 2 accessories.  
 1883, Seth Beden CS, no description of monument, no accessories given, dist. D-3 to E-3.  
 No date, CPCo, witnesses, found "T" iron and 3 new accessories.  
 1988-1989, Certified Surveys, L.2344, P.919-920, L.2380, P.873-874, L.2364, P.809-810, all by A. Vance Kupisch, PS #13586 and 3 new accessories.  
 1991, Certified Survey, L.2467, P.626-630 by Jack, N. Owens PS #20709, Ind T-iron, witnesses same as 1988-1989 A. Vance Kupisch PS #13586.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 1997 - found "T" iron at NE base of old wood fence post, and 2 accessories from 1988-1989 (tag/nail in Maple to north at 66.23' and tag/nail in maple to East at 20.20')  
  
 The "T" iron recovered monumenting the position of D-3 was most likely first found by Consumers Power Company surveyors sometime during the 1960's. Since that time the "T" iron has been found and used by A Vance Kupisch PS (1988) and by Jack N Owens PS (1991). I recovered the accessories set by Mr Kupisch in 1988 and they show that the position of the "T" iron recovered has remained unchanged. There is no recorded information that would indicate the origin and time frame when the "T" iron was set. The presence of the old fence lines E, W & S of the "T" iron along side of the anchor post show that the position of D-3 has remained the same for a long time. Upon review of this evidence I accept the position of the "T" iron along the NE side of the base of an old wooden anchor post with old fence lines to the East, West and South as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 North 66.22' Found Nail & Gould Tag in E Fc 28" Maple  
 East 20.21' Found Nail & Gould Tag in S Fc 46" Maple  
 20.28' Found Nail & Tag in S Fc 46" Maple  
 S45E 4.81' Found Nail & Tag in NE Fc 5" Ash  
 South 1.90' Found Nail & Tag in E Fc 3" Elm  
 N35W 7.95' Found Nail & Tag in SW Fc 8" Ash  
  
 Ratified by Genesee County Peer Group September 11, 1997.  
 I set the Standard Bærntsen Monument SS-A-5-BR-30 (3 1/4" D. Brass cap stamped "Genesee County Remonumentation Corner 32332, 1997") with 30" x 2 3/8" O.D. stainless steel tube with found "T" iron inside monument and set plastic base on the bottom. Due to very large piece of concrete, set Genesee County Monument is slightly leaning south, top is good.

Signed by Gilbert G. Bonno 74712 Date 9/11/97  
 Surveyor's Michigan License No. 32332

\$9.00 Filed & Rec'd