



RECORDED  
 RECEIVED  
 DEC 24 33 PM '97

1997 REMONUMENTATION PROGRAM  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

MAR 05 1998

1100 SECTION  
 Register of Deeds Stamp & File Number

For corners in	Genesee (County)	Located in:	Corner Code # I-3
1. Public Land Survey		T 6N R 8E	I-3
		T R	
		T R	
		T R	
2. Property Controlling In Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 Ratified by Peer Group in accordance with P.A. 345, 1990  
 Co. Rep. Carl Carlson  
 Date 10-30-97

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gilbert G. Bonno, P.S., in a field survey on July 28, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:**  
 1823, GLO - J. Wampler, DS; set post and 2 accessories, measured between corners I-3 and J-3 and I-3 and H-3.  
 1818, County Survey Records - J. Bishop CS post, no new accessories, measured between I-3 and I-4, and I-3 and H-3.  
 1921, GCRC - Field book and drawing #94 Hadley (Hill) Rd., no description of monument given, no new accessories, measured between H-3 and I-3 and I-3 and J-3.  
 1920's-1930's, GCRC - witnesses, no description of monument given, 5 new accessories.  
 1939, GCRC - Field book and drawing #1005, no description of monument given, no new accessories, measured between H-3 and I-3 and I-3 and J-3.  
 (Cont'd on back)
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 1997 Remon - Found 3/4" rod in a monument box ±4.5' N. of C/L Hill Road and 3 accessories from 1973 (48" oak to NE at 54.72' and 15" maple to NE at 75.49' and 14" oak to S. at 36.87') and 2 accessories from 1996 (24" shag bark oak to NNW at 41.38 and p/p to SSW at 51.88') and 3 accessories from 1997 (44" oak to NE at 54.76' and p/p to SSW at 51.88 and 24" hickory to NW at 41.38').  
 During my field work I measured down Hill road, from M-15 to Washburn road. Between H-3 & I-3 I measured 21.64' short of the 1921 GCRC record. Between I-3 & J-3 I measured 0.73' long of the 1921 GCRC record. Between I-3 & I-4 I measured 0.13 chains (8.58 feet) long of the 1848 County Surveyor record.  
 I recovered a 3/4"x10" long rod in a monument box at I-3, which was first noted as the monument in 1980, yet the size and shape of the rod was consistent with the other corners on Hill road, which suggests that the rod may have been set by the GCRC prior to 1980 when surveying Hill(Hadley) road. Unfortunately, the GCRC does not state the object monumenting I-3 in any of their drawings or field book notes. The 3/4" rod was removed and I continued to excavate inside the monument box in search of other signs of monumentation, but  
 (Cont'd on back)
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 N45E, 54.73' found double headed nail & MDOT tag in SE fc 48" Oak  
 N45E, 54.78' found PK & tag #17623 in SE fc 48" Oak  
 N45E, 54.73' found spike & GE tag in SE fc 48" Oak  
 N60E, 75.43' found spike & GE tag in S fc 16" Maple  
 N25W, 41.39' found double headed nail & MDOT tag S'ly root 20" Hickory  
 N25W41.37' found PK nail & tag #17623 in S'ly root 20" Hickory  
 N60W, 88.13' found nail & MDOT tag in S. fc 18" Hickory  
 N60W, 88.22' found nail & GE tag in NE fc 18" Hickory  
 North, 33.02' found 1/2" rod & cap "KRCarlson"  
 S15W, 51.86' found double headed nail & MDOT tag in W fc power pole  
 S15W, 51.84' found nail & tag #17623 in W fc power pole  
 S10E, 38.92' found nail & "Carlson" tag in E fc 20" Oak  
 South, 32.94' found 1/2" x 1/2" square iron bar  
 Ratified by Genesee County Peer Group October 22, 1997.  
 I set the standard Bemsten Monument SS-A-5-BR-30 (3 1/4" D. Brass cap stamped "Genesee County Remonumentation Corner 32332, 1997") with 30" x 2 3/8" O.D. stainless steel tube set in a monument box.

82486



Signed by Gilbert G. Bonno  
 Surveyor's Michigan License No. 32332

Date 10/30/97

**A. Cont'd.**

- 1973, Certified survey - L.1868, P.357-359, by E. Harris PS #9431, set tag in pavement and 5 new accessories.
- 1973, LCRC - L.1875, P.600, by R. Mitchell PS #6936, found tag, no new accessories.
- 1974, Certified Survey - L.1889, P.575-576, by G. Fauser PS #18657, found nail, 1 new accessory.
- 1974, Certified Survey by J. Albright PS #10057, found Gould Tag, no accessories give, measured between I-3 and H-3.
- 1974, LCRC, L.1904, P.215-216, by A. Kupisch PS #13586, set tag, no new accessories.
- 1980, Certified Survey - L.2082, P.789-792 by P. Pangus PS #21578, found iron in monument box, and 1 new accessory, measured between I-3 and I-2, and I-3 and J-3.
- 1982, Certified Survey - L.2157, P.961 by S. Brown PS #17613, found iron in monument box, no new accessories, measured between I-3 and I-2.
- 1996, Davison Land Surveying - witnesses, found 1/2" iron in monument box, and no new accessories.
- 1997, Unrecorded Survey - by c. Lillieburg, no description of monument given, no new accessories, measured between I-3 and I-4, and I-3 and J-3.
- 1997, Flint Surveying & Engineering - witnesses, found 5/8" re-rod in monument box 4' north of C/L E-W bit. Rd. and at tree lines to N. and S. and 1 new accessory.

**B. Cont'd**

was unsuccessful. I recovered five accessory trees from the 1920's - 1930's GCRC witnesses (unable to recover specific objects in the trees) and they were all within 0.75' of record. A fence was shown in the 1921 GCRC field notes and road plans for Hill (previously Hadley) road to the North and South of I-3. An old fence was recovered to the South of the corner and a newer split rail fence was recovered to the North. A defined tree line was recovered to the North and South of the corner. I recovered two accessories from a Certified Survey(L.1868 P.357-359) by E.B. Harris PS#9431(1973), a spike & GE tag in SE fc 48" Oak to the N45E at 54.73'(M), 54.72'(R) and a spike & GE tag in S fc 16" Maple to the N60E at 75.43'(M), 75.49'(R). I recovered numerous other accessories from the past 76 years and in some instances they measured within hundredths of a foot of record, as indicated in the above report. Upon review of this evidence; numerous recovered accessories, a defined tree line to the North and South, an old fence to the South and the half mile measurements, I accept this corner as a careful and faithful perpetuation of the position of the original corner.