

**SURVEY &
REMONUMENTATION**

MAR 05 1998

MASTER LIBER 3652 PAGE 715



SECTION

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

NOV 12 12 05 PM '97

RECORDED

For corners in

Genesee _____ (County)	Located In: ATLAS	Corner Code # I-6
1. Public Land Survey	T <u>6N</u> R <u>8E</u>	<u>I-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Filed & Recorded
9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ Ratified by Peer Group in accordance with P.A. 345, 1990

5. Private Claims _____ Co. Rep. Carl Carlson
Date 10-2-97

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gilbert G. Bonno, P.S., in a field survey on August 8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1823, GLO - J. Wampler, DS; set post and 2 accessories.
 1871, County surveyor records, S.R. Billings CS, stake, no new accessories, measured between corners H-5 & I-6.
 1966, CP Co, H.W. Dorsey, Dwg #S-F16666, no description of monument, no accessories given, measured between corners I-6 and I-7.
 1984, Certified survey, L.2231, P.919, by C.S. Getz, P.S. #25843 1/2" iron, 4 new accessories, measured between corners I-6 and I-7.
 1993, Certified survey, L.2564, P.656-657 by C.H. Carlson P.S. #9189 found 1/2" smooth bar in fence line, 4 new accessories given.
 1993, LCRC L.2525, P.166, by H.H. Kennedy PS #17623, found 1/2" rod in N-S fence line, no accessories given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1997 Remon - Found 1/2" smooth bar in N-S wire fence line. One accessory from 1984 (nail/bottle cap in fence post to the south at 4.50'), four accessories from 1993 (PK and tag in 12" hickory to the east at 25.90', PK/tag in 10" walnut to the NE at 25.63', PK/tag in 8" hickory to the SW at 13.72', and PK/tag in 16" hickory to the NW a 28.95').

In 1984 Charles Getz PS#25843 reported having a 1/2" iron at this corner. Prior to this time no description of monumentation had been given since the original GLO survey in 1823 by J. Wampler. In 1984 Mr. Getz indicates setting 3 accessories, 1 of which I found, the nail and bottle cap in fence post at 4.5 feet. Today I find it at the same distance of 4.5 feet. He also notes a measurement of 2630.25 feet, which agrees within 0.27 feet of a 1966 consumers measurement of 2629.98 feet. Consumers does not indicate finding any type of monumentation at this corner. It appears that they measured the total mile and split the measurement to establish I-6. In 1992 Mr. Huston Kennedy PS#17623 reported finding a 1/2" iron rod at this corner and set 4 new accessories. I found all 4 of these accessories and agreed within hundredths of a foot of his measurements. In 1993 Mr. Carl Carlson PS#9189 reported finding a 1/2" rod at this corner and showed the same accessories as Mr. Kennedy in 1992. Today in my Remonumentation work I am finding the 1/2" rod that has been reported since 1984 in a north-south fence row with fence running west only. I found or received no information on when the 1/2" rod came into being. In my field research I excavated down approximately 2 feet and found no evidence of a wood post as indicated in the GLO notes of 1823. This corner is situated in a wooded area, which is surrounded by farm fields and has seen very little activity for development. I accept the position of the 1/2" smooth bar in the N-S fence line as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 South, 4.50' found nail & bottle cap in W fc fence post
 East, 25.91' found PK & "HKK" tag in N fc 12" Hickory
 N30E, 25.64' found PK & "HKK" tag in NW fc 10" Walnut
 S30W, 13.72' found PK & "HKK" tag in NW fc 8" Hickory
 N45W, 28.94' found PK & "HKK" tag in S fc 18" Hickory

Ratified by Genesee County Peer Group October 2, 1997.
 I set the standard Bernsten Monument SS-A-5-BR-30 (3 1/4" D. Brass cap stamped "Genesee County Remonumentation Corner 32332, 1997") with 30" x 2 3/8" O.D. stainless steel tube with plastic base.

77513

Signed by Gilbert G. Bonno
 Surveyor's Michigan License No. 32332

Date 10/2/97