



RECORDED
 DEC 2 4 33 PM '97
 GENESSEE COUNTY

1997 REMONUMENTATION PROGRAM
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

MAR 05 1998

SECTION

900
 Register of Deeds Stamp & File Number

For corners in

Genesee (County)	Located In:	Corner Code # K-7
1. Public Land Survey	T 6N R 8E	K-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Ratified by Peer Group in accordance with P.A. 345, 1990
 Co. Rep. Carl Carlson
 Date 10-30-97

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gilbert G. Bonno, P.S., in a field survey on July 30, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:**
- 1823, GLO - J. Wampler, DS; set post and 2 accessories, measured between corners K-7 and L-7 and J-7 and K-7.
 - 1869, County Surveyor - S.R. Billings CS, stone, no new accessories.
 - 1890, County Surveyor - M. Middleton CS, stone and 2 new accessories, measured between J-7 and K-7.
 - 1919, GCRC - Dwg. & field book 3845 (Hegel Rd.), pipe and stone, no accessories given, measured between J-7 & K-7 and K-7 & L-7.
 - 1920's-1930's, GCRC - witness card, pipe in concrete, and 5 new accessories.
 - 1966, CPCo - H.W. Dorsey, found iron under concrete, set "T" iron to bring to surface and 2 new accessories, measured between K-7 and L-7 and K-7 and K-6.
 - 1977, LCRC - L.1992, P.189, by J. Albright PS #10057, "T" iron in monument box, and 2 new accessories.
 - 1987, Gould Engineering - Witness card, found 1/2" re-rod in monument box, and 2 new accessories.
 - 1994, Certified Survey - L. 2527, P.108, by C.H. Carlson PS #9189, found 5/8" rod in monument box, and 2 new accessories.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**
- 1997 Remon - Found 1/2" rod in monument box above a "T" iron, above a pinch pipe. Monument box is ±1' south of centerline Hegel Road and ±2.5' west of centerline Henderson Road. I recovered 2 accessories from 1966 (telephone box to the SW at 60.70', and anchor post to the NW at 45.90') and 1 accessory from 1977 (fnc. post to the SE at 45.92').

In 1919 the GCRC states a pipe(pinch pipe?) and stone monumenting K-7, in 1966 CPCo found an iron (pinch pipe?) under concrete and set a "T" iron to bring to surface. The "T" iron was recovered in 1977 by J. Albright PS#10057 in a monument box. In 1987 Gould Eng. found a 1/2" rerod in a monument box. In 1994 C. Carlson PS#9189 found a 5/8"(1/2") rod in a monument box. This time frame of different monumentation coincides with what I recovered during my field investigation. My research indicates that the corner position of K-7 has been in the same location since it was monumented as a pipe and stone in 1919 by the GCRC. I did recover one accessory from 1966 CPCo; SW 60.70'(H) center of telephone box, I measured 60.23' to the top center of telephone box, and I recovered one accessory from 1977; S45E 45.92'(R) corner fence post, I measured 45.70' to a found PK nail in ENE fc wood A. post. Despite my efforts to recover the stone the County Surveyors called for in 1869 and 1890, I was unsuccessful, but note that it appears that the road was raised considerably from original grade (+/- 4 feet). Upon review of this evidence, I accept the position of the found pinch pipe as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- S45E, 45.72' found nail & tag #17623 in E fc wood A. Post
 - S45E, 45.70' found PK nail in ENE fc wood A. Post
 - S45W, 60.60' found nail & tag #10007 in top of cut off cut off pole next to telephone box
 - S45 W, 60.23' top center of telephone box
 - S40W, 76.29' found K. Carlson nail & tag in NW fc twin 8" Willow
 - N40W, 44.40' set PK & Genessee County Witness tag in SW fc light pole
 - S40E, 77.00' found K. Carlson nail & tag in NE fc 8" Cottonwood

Ratified by Genessee County Peer Group October 2, 1997.
 I set the standard Bernsten Monument SS-A-5-BR-30 (3 1/4" D. Brass cap stamped "Genessee County Remonumentation Corner 32332, 1997") with 21" x 2 3/8" O.D. stainless steel tube set in Quickcrete.

82488

Signed by Gilbert G. Bonno
 Surveyor's Michigan License No. 32332

Date 10/30/97
10/2/97