

MAY 20 1997

COMMISSION

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MASTER LIBER 3436 PAGE 808

RECORDED
REGISTERED
FEB 30 11 37 AM '95

For corners in

Genesee (County) Located In: Corner Code #

1. Public Land Survey T 7N R 5E A-5

2. Property Controlling in Section S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LCRC 83501

Register of Deeds Stamp & File Number

I, Kevin B. Cleaver P.S. in a field survey on November 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1821 GLO Set post with two (2) accessories
 Oct 11, 1930 Michigan Department of Transportation construction plans
 1934 Genesee County Road Commission Construction plans
 Date ? Gould Engineering, Inc. records, Nail in center line of road with three (3) accessories
 July 3, 1986 LCRC Liber 2305, Page 497, with three (3) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

Ratified by Peer Group in accordance with P.A. 345, 1990
 Co. Rep. Carl Carlson
 Date 10-15-96

We re-established the corner by using the three (3) accessories from the LCRC Liber 2305, Page 497. We found these ties to place the corner on the east town line T7N-R4E. We found this location to also fit the construction plans of 1930 and 1934.

The method used to re-establish this corner was ratified by the Genesee County remonumentation committee on October 15, 1996 as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set in concrete the standard Bernsten monument SS-A-5-BR-30 with 3/4" brass cap stamped Genesee County Remonumentation Corner 1996, #29242 in a monument box.

S 45° E 53.70' Southeast corner of east and west headwall
 S 50° W 48.70' Set remon tag in north face 14" Maple
 N 70° W 43.86' Set remon tag in north face 14" Ash
 N 45° E 54.50' Northeast corner of east and west headwall

Signed by Kevin Banfield Cleaver Date Nov 22, 1996
 Surveyor's Michigan License No. 29242

