

MAY 20 1997

COMMISSION

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Genesee

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 7N R 5E C-4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

83533

RECORDED
DEC 30 11 37 AM '96

RECORDED
900

FILED & RECORDED

Register of Deeds Stamp & File Number

I, Kevin B. Cleaver, PS, in a field survey on October 18, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1821, GLO Set post with two (2) accessories
- Date ? Gould Engineering, Inc., found stone with three (3) accessories
- May 30, 1973 Certified survey Liber 1857, page 13, found 3/4" pipe, with three (3) accessories
- Nov. 17, 1976 L.C.R.C. Liber 1977, page 797, found 3/4" pipe, with three (3) accessories
- Oct. 14, 1993 Certified survey Liber 2515, pages 726 and 727, found pipe, with five (5) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found pinch pipe in gravel road; found two (2) accessories from Gould Engineering, Inc. records found three (3) accessories from survey Liber 1857, page 13; found three (3) accessories from L.C.R.C. Liber 1977, page 797; found five (5) accessories from survey in Liber 2515, pages 726 and 727.

The monument found was ratified by the Genesee County Peer Review Committee on October 9, 1996, as the accepted corner.

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep Land
Date 10-9-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30, with 3 1/4" brass cap stamped Genesee County Remonumentation corner 1996, #29242 over found pinch pipe in gravel road.

- N 40° W 61.11' Found nail and tag #23857 in Northeast face of twin 8" elm
- N 45° W 43.66' Found nail and tag #23857 in Northeast face of 12" elm, set remon. tag over
- S 45° E 42.93' Found nail and tag #23857 in Southwest face of 15" oak
- N 40° E 45.61' Set remon. tag in Northwest face of 40" oak

Signed by Kevin Banfield Cleaver
Surveyor's Michigan License No. 29242



Oct 18, 1996