

MAY 20 1997

COMMISSION

1996 REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Genesee (County) Located In: Corner Code ##
1. Public Land Survey T 7N R 5E E-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

83537
RECORDED
DEC 30 11 37 AM '96
REGISTER OF DEEDS STAMP & FILE NUMBER

I, Kevin B. Cleaver, P.S. a field survey on October 18, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at row 5, column D.

A. Description of original monument and accessories and/or subsequent restoration:
1821, GLO Set post with 2 accessories
Date ? GEI records, iron pin with 8 accessories
July 2, 1971 Survey L-1810, P-794, 795, 1/2" iron with 3 accessories
March 7, 1973 LCRC, L-1849, P-582, fnd iron pin, with 3 accessories
July 25, 1977 Survey L-1984, P-730, 731, 3 accessories
Dec. 30, 1980 Survey L-2104, P-226, fnd 1/2" iron with 3 accessories
April 14, 1987 LCRC, L-2305, P-494, fnd 3/4" rod with 4 accessories
Aug. 17, 1990 Survey L-2405, P-336, fnd 1/2" rod, with 4 accessories
Nov. 22, 1993 Survey L-2549, P-813, 814; Survey L-2521, P-282, 283; Survey L-2525, P-680, 681, fnd 1/2" rod with 4 accessories
March 17, 1995 Survey L-2576, P-810, 811, fnd 3/4" pin with 4 accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Fnd 3/4" pinch pipe over a large stone; fnd 1 accessory from GEI; fnd 1 accessory from July 2, 1971 survey; fnd 1 accessory from March 7, 1973 survey; fnd 1 accessory from July 25, 1977 survey; fnd 1 accessory from Dec. 30, 1980 survey; fnd 3/4" iron and 1 accessory from April 14, 1987, LCRC; fnd 4 accessories from Aug. 17, 1990 survey; fnd 4 accessories from Nov. 22, 1993 survey's; fnd 3/4" pin and 4 accessories from March 17, 1995 survey.

The monument found was ratified by the Genesee County Peer Review Committee on October 9, 1996.
Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlson
Date 10-9-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set in concrete the standard Bernsten monument SS-A-5-BR-30, with 3/4" brass cap stamped Genesee County Remonumentation Corner 1996, #29242 over a 3/4" pipe over a large stone.
S 60° W 134.67' Fnd Northeast corner of barn foundation
S 45° W 34.97' Fnd notch in top of South end of 18" CMP
N 35° W 37.73' Fnd notch in top of North end of 18" CMP
N 45° W 61.98' End PK/washer in Southeast face 14" CATAUPA

Signed by Kevin Banfield Cleaver, P.S. Its Field Manager
Surveyor's Michigan License No. 29242
Date Oct 18, 1996

