

MAY 31 2000

SECTION

1996 REMONUMENTATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Genesee

(County)

Located In:

Corner Code-#

1. Public Land Survey	T	7N	R	5E	F-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

83538

RECORDED  
Dec 30 11 37 AM '96

900

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kevin B. Cleaver, P.S. in a field survey on October 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1821, GLO	Set post	Sept. 24, 1984	Cert. survey, L-2207, P-653, 654
Date ?	GEI records	Dec., 1986	GEI records
July 29, 1973	Cert. survey, L-1860, P-191, 192	Aug. 17, 1990	Cert. survey, L-2405, P-336
April 6, 1976	Cert. survey, L-1339, P-925	June 1, 1993	Cert. survey, L-2502, P-848, 849
July 25, 1977	Cert. survey, L-1984, P 730, 731	July 2, 1993	Cert. survey, L-2504, P-594, 595
Oct. 22, 1979	Cert. survey, L-2066, P-635-637	March 23, 1995	Cert. survey, L-2576, P-810, 811
May 19, 1980	Cert. survey, L-2085, P-400	Sept. 9, 1995	Cert. survey, L-2597, P-385, 386
Dec. 30, 1980	Cert. survey, L-2104, P-226	Sept. 21, 1995	LCRC, L-2592, P-683

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" re-rod in gravel; found 1/2" rod and one (1) accessory from Dec. 30, 1980 survey; found 1/2" rod and four (4) accessories from Aug. 17, 1990 survey; found 1/2" rod and four (4) accessories from June 1, 1993 survey; found 1/2" rod and four (4) accessories from July 2, 1993 survey; found 1/2" rod and four (4) accessories from March 23, 1995 survey; found 1/2" rod and six (6) accessories from Sept. 9, 1995 survey; found 1/2" rod and four (4) accessories from Sept. 21, 1995 LCRC.

The monument found was ratified by the Genesee County Peer Review Committee on October 15, 1996, as the accepted corner.

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep Carl Jackson  
Date 10-15-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30, with 3/4" brass cap stamped Genesee County Remonumentation Corner 1996, #29242 over 1/2" re-rod in gravel.

N 13° W	35.82'	Found nail/tag #23857 in West face of 8" hickory
S 30° E	39.24'	Found nail/tag in West face of 12" spruce
S 16° W	34.30'	Found 1/2" rod/cap #33134
North	39.40'	Found nail/cap #35992 in West face of 5" hickory



Signed by Kevin Banfield Cleaver Date Oct 18, 1996  
Surveyor's Michigan License No. 29242

89