

MAR 16 1994

DEED LIBER 2520 PAGE 928

COMMISSION

REMONUMENTATION CORNER UNDER ACT 345, MICHIGAN PUBLIC ACTS OF 1990

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
REGISTERED  
DEC 27 9 11 AM '93  
GENESEE COUNTY  
FLINT MICHIGAN

For corners in

GENESEE

(County)

Located In:

*Flint Top*

Corner Code #

1. Public Land Survey	T	7N	R	6E	F-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

77979

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_


A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DONALD G. RICHARDS, in a field survey on December 22nd, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Horatio Ball/Hervey C. Parke  
Sunday September 16th or Monday the 17th, 1821  
W Ash 10 S 62 E 20  
W Ash 7 N 18 W 12  
(see reverse side for additional information)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Using points recovered in SUPERVISOR'S PLAT NO. 9 (Liber 17, Page 14) established Section line from corner E-3, T7N-R6E, East to intersection of Section 11 of "Reservation of Eleven Sections at and Near the Grand Traverse of the Flint River"; set quarter corner at a distance of 40.00 chains proportionate measure from corner E-3

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Bernsten monument SS-A5BR-30 stamped "Genesee County Remonumentation Corner" with iron inside 5.62' at right angles from foundation wall of brick building # 2069  
WEST 77.03' nail/GCWT\* in S face 15" Sumac  
N 15 W 107.22' nail/GCWT in S side steel chain link fence post  
N 15 E 34.31' NW corner of brick building #2069  
SOUTH 8.42' SW corner of brick building #2069  
WEST 2645.57' section corner E-3, T7N-R6E  
(\* Genesee County Witness Tag)

Signed by DONALD G. RICHARDS *[Signature]* Date December 23, 1993

Surveyor's Michigan License No. 24614

APPROVED by Genesee County Monumentation Peer Group 12-21-93

PLATS

DEED  
LIBER 2520 PAGE 929

Ora F. Gould, February 23rd, 1932  
SUPERVISOR'S PLAT NO. 9, 17/14  
unidentified and undepicted (SE corner of Government Lot 6 falls  
within interior of Platted Lot 11)

GCRC TIES

none

PA 74

none

PA 132

none