



1998 REMONUMENTATION PROGRAM
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
 GENESSEE COUNTY
 101246
 Nov 25 8 04 AM '98
Micki...

For corners in _____
 Located In: Burton Twp. Corner Code # D-11

 (County)

- 1. Public Land Survey T 7N R 7E D-11
 T R
 T R
 T R
- 2. Property Controlling in Section S T R
 S T R
- 3. Miscellaneous Property in Sec. S T R
 S T R
- 4. Lot No. _____, Recorded Plat _____ SECTION _____
- 5. Private Claims _____

SURVEY &
 REMONUMENTATION

Register of Deeds Stamp & File Number

MAR 17 1999

I, Gilbert G. Bonno, P.S., in a field survey on September 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1821 GLO - J. Wampler, Set post and 2 accessories
- 1920's-1930's GCRC Witnesses, Pipe and stone
- 1919 Atherton Homestead No. 1 - Steel Stake; shown on centerline of Bristol Road at intersection of 1/4 line.
- 1919 Atherton Homestead-No description of monument given; shown on centerline of Bristol Rd. at intersection with west line of plat.
- 1919 Atherton Homestead No. 2 - No description of monument given; shown on centerline of Bristol Road at intersection with east line of plat.
- 1935 Supervisors Plat No. 25 - One inch iron rod in pavement; shown on centerline of Bristol Road at intersection with far west line of plat. Distance between 1/4 corner and NE corner of Section 32 is 2618.10'.
- 1960's GCRC Dwg. #218 - One inch iron in Bristol Road.
- 1971 LCRC by N.C. Jones #02934 L.1820, P.332 - 1 1/2" iron at concrete pavement surface.
- No date GCRC Dwg. #1020 - No description of monument given; distance from SE corner Baker Park plat to S 1/4 corner 2653.25'; distance from S 1/4 Section 29 to SE corner - 2618.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Remon
 Found 1" rod in concrete under 4" of asphalt. In 1821, J. Wampler, D.S. set a post and two accessories for corner D-11 midway and on line between corners C-11 and E-11. A distance from C-11 to D-11 of 39.79 chains (2626.14 feet) (1998, 2651.81 feet). D-11 to E-11 of 39.79 chains (2626.14 feet) (1998, 2618.66 feet). Neither of the accessories exist in 1998. In the 1920's - 1930's, a pipe and stone is indicated for corner D-11. Six accessories are indicated none of which exist in 1998. In the 1919 Plat of Atherton Homestead No. 1, D-11 is called out as a steel stake and shown in the centerline of Bristol Road at intersection of 1/4 line. Again in 1919, in the Plat of Atherton Homestead No. 2, D-11 is shown at the centerline of Bristol Road at intersection of East Line of plat. No description is given for C-11. In 1935, Supervisors Plat No. 25 indicates a 1" iron rod in pavement, shown on centerline of pavement. Distance from D-11 to E-11 of 2618.10 (1998, 2618.66 feet). In 1960's Genesee County Road Commission road plans #218 indicate a 1" iron in Bristol Road with three accessories. None of which exist in 1998. In 1971, N.C. Jones P.S. #2934 in a recorded LCRC L1820, P332 indicates a 1 1/2" iron in concrete pavement. Four accessories are shown, three of which exist in 1998 and check very well. On Genesee County Road Commission plans (no date) dwg# 1020 a distance from corner D-11 to E-11 of 2618.3 feet is shown (1998, 2618.66 feet).

In the 1998 remonumentation program, I am finding a 1" rod in concrete under four inches of asphalt. Three accessories from the 1971 survey by H.C. Jones are being found and check very well compared to record. Distances between corners D-11 to E-11 of 2618.10 (1935); 2618.3 (no date) and 2618.66 (1998) indicate that D-11 has remained in the same position since 1935. I accept the found 1" rod in concrete under 4" of asphalt as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- S10W 25.49' Found 'MDSH' tag & Duplex nail in E. fce P/P
- S75E 50.64' Set chiseled 'X' on S. rim of storm manhole between concrete curb and concrete sidewalk
- N50E 50.90' Set chised 'X' on SE corner of catch basin
- N25W 42.44' Found large PK nail & brass tag in NE face of a twin 20" Box Elder
- N05W 34.78' Found Michigan State Highway B.M. tag & PK nail in E. Face of a twin 16" Box Elder
- N15W 34.81' Set G.C. remon tag & P.K. nail in SW fce P/P
- West 149.55' Centerline/Centerline intersection of Fern Ave. and Bristol Rd.

Ratified by Genesee County Peer Group September 30, 1998. I set the standard Bernsten Monument SS-A-5-BR-30 (3 1/4" D. brass cap stamped "Genesee County Remonumentation Corner 32332, 1998) with 30" x 2 3/8" O.D. Stainless Steel Tube with Plastic Base.

Ratified by Peer Group in accordance with P.A. 345, 1990
 Co. Rep. Carl H. ...
 Date 10-7-98

Signed by Gilbert G. Bonno Date 10/7/98
 Surveyor's Michigan License No. 32332