

MAY 31 2000

SECTION

MASTER LIBER 3995 PAGE 284



1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

GENESEE COUNTY REGISTER OF DEEDS

NOV 25 8 05 AM '98

McL...
\$9.00
Book

101249

Register of Deeds Stamp & File Number

For corners

Genesee (County) Located In: Burton Twp. Corner Code # G-11

- 1. Public Land Survey T 7N R 7E G-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gilbert G. Bonno, P.S., in a field survey on September 19 98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management, or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1815 GLO - J. Wampler, D.S. Set post and 2 accessories
- 1920's 1930's GCRC Witnesses - pipe.
- 1921 GCRC Road Plans Dwg. #1014 No description of monument given; shown at intersection of Bristol Road and centerline of Center Road.
- 1926 Scram Acres - No description of monument given; shown at intersection of Bristol Road and centerline of Center Road, G-11, G-10 2612.3'
- 1930 GCRC Road Plans Dwg #1006 - No description of monument given; shown on centerline of Bristol Road at intersection with Center Road (gravel), H-11, G-11 2629.18'
- 1947 GCRC Road Plans Dwg #338 - No description of monument given; shown at intersection of centerline of Center Road & centerline of Bristol Road G-11, G-12 2651.78'.

(Cont'd on Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Remon
Fnd. 1/2" O.D. pipe in monument box at the intersection of the centerline of Bristol Road and centerline of Center Road. In 1821 J. Wampler, D.S. set a post and 2 accessories for corner G-11 at 40 chains (2640 feet) north of corner G-12. In 1998 neither of the accessories exist and the measurement between G-12 to G-11 is 2651.06 feet (40.17 chains). In the 1920's-1930's Genesee County Road Commission notes indicate a pipe for and 6 accessories for this corner. Road plans for this area indicate G-11 at the intersection of the centerlines of Bristol Road and Center Road. None of the 6 accessories exist in 1998. In 1926 the plat of Schram Acres L. 13, P. 44 was put on by Gerald Smith, showing the corner at the intersection of the centerlines of Bristol Road & Center Road. No description of the monument is given. In 1998 this intersection is 5 lanes but G-11 is in the center of both roads. From the 1940's to 1972 the corner is continually being shown at the intersection of the centerlines for Bristol and Center Roads with no description of the monument given. From 1977 to 1990 in various certified surveys and county road plans G-11 is called out as a pipe in monument box with several of the accessories being set for this corner over that time frame still in place in 1998, all check from 0.01 to 0.03 feet of record.

(Cont'd on Back)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- S45E 70.680' Found Stainless Steel Tag "Survey Point, Do Not Disturb" Tag & Nail in SW Fc P/P
- S45E 78.270' NW Cor. Conc. Base of possibly old Kayo sign, Now Rainbow Video sign
- S40W 68.325' Found Gould Stainless Steel Tag & Nail in NW Fc P/P
- N45W 67.160' Found Gould Stainless Steel Tag & Nail in SW Fc P/P
- N45E 70.970' Found Gould "T" Iron & Stainless Steel Tag
- N40E 63.905' Found Gould Stainless Steel Tag & Nail in NW Fc P/P

Ratified by Genesee County Peer Group September 30, 1998. I set the standard Bernsten Monument SS-A-5-BR-30 (3 1/4" D. brass cap stamped "Genesee County Remonumentation Corner 32332, 1998) with 30" x 2 3/8" O.D. Stainless Steel Tube with Plastic Base. Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. [Signature] P.S.
Date 10-7-98

Signed by Gilbert G. Bonno Date 10/7/98 Surveyor's Michigan License No. 39096

92