

**SURVEY &
REMONUMENTATION**

MAY 31 2000

SECTION

MASTER LIBER 3995 PAGE 285



**1998 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in _____

Genesee Located In: Burton Twp. Corner Code # H-11
(County)

- | | | | |
|---------------------------------------|---|---|-------|
| 1. Public Land Survey | T | R | H-11 |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S | T | _____ |
| | S | T | _____ |
| 3. Miscellaneous Property in Sec. | S | T | _____ |
| | S | T | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims _____ | | | |

GENESEE COUNTY REGISTER OF DEEDS
101250
Register of Deeds Stamp & File Number

Nov 25 8 05 AM '98
M. J. Kelly, M.C.L.
\$9.00
F. Kelly

I, Gilbert G. Bonno, P.S., in a field survey on September 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1815 GLO - J. Wampler, D.S. Set post and 2 accessories
- 1956 GCRC Road: plans dwg. #1341 - no description of monument given; shown at intersection of centerline Howe Road and centerline Bristol Road, H-11, G-11 2623.00'; I-11, H-11, 2617.94'
- 1977 LCRC L.2125, P.135 Elbex B. Harris #9431 - 3/8" rod in monument box.
- 1978 Rowe Witnesses - Iron pine
- 1986 Certified Survey L.2278, P.355 - 1" bolt spike in pavement.
- 1989 Survey Carl H. Carlson #9189 - 1" iron in monument box
- 1990 Certified survey L.2403, P.403-4 Victor J. Lukasavitz - 1" round rod in monument box
- 1997 Certified survey L.3571, P.151 Charles T. Lillieburg #40162 - 3/4" rod in monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Remon

Found 1" iron rod in monument box at intersection of centerline Bristol Road and centerline Howe Road. In 1821, J. Wampler D.S. set a post and 2 accessories for corner H-11 on a straight line and midway between corners G-11 and I-11. Measurements between G-11 and H-11 of 39.89 chains (2632.74'); H-11 & I-11 of 39.89 chains (2632.74'). In 1998 I measure between G-11 and H-11 2623.34 ft; H-11 & I-11 2617.97'. In 1956 the first record of corner H-11 shows up since the 1821 GLO survey showing the corner H-11 at the intersection of the centerlines of Howe & Bristol Roads. A measurement from G-11 to H-11 of 2623.00 ft (1998, 2623.34 ft); H-11 to I-11 of 2617.94 ft (1998, 2617.97 ft). No description of the object in place for corner H-11 is given in the 1956 GCRC plans Dwg. #1341. In 1977 Elbex Harris PS #9431 in a LCRC recorded in L.2125, P.135 indicates a 3/8" rod in monument box with 7 accessories for corner H-11. In 1998 I am finding 3 of these accessories which check very well against the 1977 survey. In 1978, Rowe witnesses indicate an iron pin and 7 accessories, 2 of which exist in 1998 and check very well. In 1986 a certified survey L.2278, P.355 and a LCRC L.2278, P.357 by G. Bonno PS #32332 indicate a 1" bolt spike in pavement (no indication of monument box) with 4 accessories, 3 of which exist in 1998, all of which check very well. In 1989 Carl Carlson indicates a 1" iron in monument box, with 3 accessories, 2 of which exist in 1998 and check very well. In 1990 a certified survey L.2403, P.403-404 by Victor Lukasavitz a 1" round rod in monument box is called for with 5 accessories, 2 of which exist in 1998 and check very well. In 1997 a certified survey L.3571, P.151 by Charles Lillieburg PS #40162 indicates a 3/4" rod in monument box with 4 accessories all of which exist in 1998 and check very well.

(Cont'd on Back)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- S80E 206.69' Found Kraft Rod & Cap
- S35E 60.24' Found Kraft Rod & Cap
- S35E 42.70' Found Old Sign Post base in shoulder, approx. 0.5' below ground level
- S45W 45.64' Found Chiseled Square on Top of R/W Marker
- S65W 60.58' Found Gould Stainless Steel Tag & Nail in NW Fc P/P
- S45W 70.00' Found Gould Stainless Steel Tag & Nail in SW Fc P/P
- N25E 118.11' SW Corner of Block Foundation to Hse. #4267
- N45E 91.25' Found Davison Yellow Rerod Cap #40162 & Nail in SE Fc 22' Maple
- North 50.19' Plat Corner Iron Pine-Bent
- N60E 91.32' 40162 Tag in SE Fc 28" Hickory

Ratified by Genesee County Peer Group September 30, 1998. I set the standard Bernsten Monument SS-A-5-BR-30 (3 1/4" D. brass cap stamped "Genesee County Remonumentation Corner 32332, 1998) with 30" x 2 3/8" O.D. Stainless Steel Tube with Plastic Base.

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. Carl H. Carlson P.S.
Date 10-7-98

Signed by Gilbert G. Bonno
Michigan License No. 39096

Date 10/7/98 Surveyor's