# GILBERT G. * BONNO PROFESSIONAL # SURVEYOR	1998 REMO	NUMENTATION PROG	MASTER 39		272
SURVEYOR O	LAND CORNER	RECORDATION CERT	ΓΙΓΙCATE		
32332 Aron	Filing Requirer	nent of Act 74, Mich. P 	.A. 1970	SESE SE	75
Genesee Located In: (County)	ಕೆಲ್ಲಾಗು: : Twp. Corner C	ode #M-12		OF DEE	Bo. Hit To B
1. Public Land Survey T_	7 R 7 K-12		10	1237	
Z. Property Controlling S T In Section S T 3. Miscellaneous S T Property in Sec. S T	R R R R R R R R R R R R R R R R R R R	SURVEY & LONUMENTATION	Register of Deeds S	-	umber
3. Miscellaneous S T Property in Sec. S T	R	MAR 1 7 1999			
			, A B C D) E F G H	IJKLN
4. Lot No, Recorded Plat 5. Private Claims		SECTION	2 6 5	4··· 3··	2 1
I, Gilbert G. Bonno , In a	a field survey on <u>Sミタフさ</u>	<u>im Jer 1998</u>	4 7 8	9 10	11 12
do hereby certify that under requirements in lines 1 and 2 above were in conformar current manual of survey instructions of the	nce with regulations and le United States Departme	rules therefore as required	in the 6 18 17	7 16 15	14 13
Management or by a decree of a Court of La above were in conformance with the rules Court of Law; established, re-establish	aw and/or that the corner; of the Michigan Board of	points mentioned in lines 3, 4 Land Surveyors or by a Decre	and 5	21 22	23 24

Description of original monument and accessories and/or subsequent restoration:

GLO Notes J. Wampler D.S. Set post and two accessories 1821

NOTE: Not more than 2 corners, all in the same town and range, may be recorded

expressed below:

on this certificate.

1920's GCRC Dwg #1008 No description of monument given; shown in centerline of Belsay Road

Survey and field notes Flint Surveying Carl Carlson PS #9189 1" Pipe in monument box and 3 accessories 1988

Description of corner evidence found and/or method applied in restoring or reestablishing corner: B.

1998 Remon: Found Monument Box with 1" pipe at centerline Belsay Road

In 1821 J. Wampler DS set a post with two accessories for corner K-12, 40 chains (2640') north of corner K-13. Neither of the accessories exist in the 1998 Remonumentation Program. He then continued 40 chains (2640') North of K-12 to set K-11. In the 1920's Genesee County Road Commission drawing no. 1008, show corner K-12 in the centerline of Belsay Road but give no description of the object in place. The plans showed a measurement between corner K-13, K-12 of 2650.2 feet (1998, 2650.03 feet). Also a measurement between corners K-12, K-11 of 2644.3 feet, (1998, 2643.05 feet). Genesee County witnesses, no date show four accessories set, none of which exist today, also no description of the object in place is given. The next record of this corner appears in 1988 in a survey by Flint Surveying, CarlCarlson PS #9189. Mr Carlson indicates finding a 1" pipe in monument box at this corner. He also indicates setting three accessories, none of which exist in 1998.

In the 1998 Remonumentation Program, I am finding a 1" pipe in monument box in the centerline of Belsay Road. My measurement between corners K-13, K-12 of 2650.03', checks within 0.17 feet of the 1920's GCRC measurement of 2650.2 feet. The 1920's plans also indicated finding corner K-12 in the centerline of Belsay Road as we are in 1998. I accept the position of the 1" pipe in monument box as the best available evidence of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Monument Box with 1" Pipe @ Centerline Belsay Road N34°E 57.92' Fnd K. Carlson nail & tag SW face PP

Ratified by Genesee County Peer Group November 18, 1998. I set the standard Bernsten Monument SS-A-5-BR-30 (3 1/4" D. brass

10

11

12

30

31

29

32

28

33

27

34

26

35

25

36

N45°W 70.32' Fnd K. Carlson nail & tag SE face PP S36°W 79.72' Fnd nail & tag 32332 in E'ly face of PP S35°E 80.60' Fnd K. Carlson nail & tag NE face of PP	cap stamped "Genesee County Remonumentation Corner 32332, 1998) with 30" x 2 3/8" O.D. Stainless Steel Tube with Plastic Base.
	atified by Peer Group in ecordance with P.A. 345, 1990 Date 1//12/28 Surveyor's
ichigan License No. <u>3253 ८</u>	ALPITED FOR WORD PROCESSING MARCH, 1993
The same of the sa	