

MAR 17 1999

1998 GENESEE COUNTY REMONUMENTATION PROGRAM SECTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MASTER LIBER 4013 PAGE 122

For corners in

<u>Genesee County</u>	Located In:	Corner Code #
1. Public Land Survey	T7N R7E	L-11
2. Property Controlling in Section	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____

106850

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

I, Kevin B. Cleaver, in a field survey on November 6, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 7-21-1821 General Land Office (GLO) fieldnotes: set post w/two accessories
 Undated Gould Engineering, Inc. (GEI) records: stake w/seven accessories
 Undated GEI records: T-iron w/four accessories
 11-19-1965 recorded plat "Brisdale": dimensioned to section corner
 5-16-1978 PA 132 Certified Survey, Liber 2009, Page 129: monument box w/three accessories, and 1/2 mile measurement
 2-27-1979 Land Corner Recordation Certificate (LCRC), Liber 2034, Page 408: monument box w/three accessories
 4-21-1989 LCRC, Liber 2369, Page 462: 1 1/4" iron in monument box w/three accessories
 6-20-1998 GEI records: 1 1/4" iron in monument box w/four accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 GLO corner and accessories not found
 Corner and accessories from both set of undated GEI records not found
 Confirmed within acceptable tolerance 1965 platted dimensions to section corner
 Recovered monument box and one accessory, and confirmed within acceptable tolerance the half-mile measurement from 1978 recorded survey
 Recovered monument box and two accessories from 1979 LCRC
 Recovered corner as identified and three accessories from 1989 LCRC
 Recovered corner as identified and four accessories from 1998 GEI records

The monument found was ratified by the Genesee County Remonumentation Peer Review Committee on November 4, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set in concrete the standard Bernsten monument SS-A-5BR-30 with 3 1/4" brass cap stamped "Genesee County Remonumentation Corner, 1998, #29242" over 1 1/4" rod in monument box.
 N 60° W 97.11' set Genesee County Witness tag in southwest face power pole
 NORTH 12.06' north edge of concrete pavement
 N 65° E 115.91' set Genesee County Witness tag in northwest face power pole
 S 20° E 52.51' found nail/tag #32332 in west face power pole
 S 30° W 46.23' found chiseled notch west end 18" corr. culvert

Ratified by Peer Group in accordance with P.A. 345 1990
 Co. Rep. Carl Larson
 Date 11-4-98

Signed by Kevin Banfield Cleaver Date 12/8/98
Kevin Banfield Cleaver, P.S.

Surveyor's Michigan License No. 29242

