

SURVEY & REMONUMENTATION

MAR 23 2000

**1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

Michael J. MacLean

For corners in

SECTION
Genesee County

Located In: Davison

Corner Code # C-5

Dec 28 10 37 AM '99

GENESEE COUNTY
REGISTER OF DEEDS

4358, P 735

Register of Deeds Stamp & File Num

1. Public Land Survey	T	7N	R	8E	C-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T		R	
	S	T		R	
3. Miscellaneous	S	T		R	
Property in Section	S	T		R	

4. Lot No. _____ Recorded Plat _____
5. Private Claim _____

I, David J. Kenney, in a field survey on November, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	16		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 G.L.O. Joseph Wampler D.S.
- 1928 G.C.R.C. Stake, 1 accessory
- 1974 L.C.R.C. L1898, P. 519 by Lyl H. Howison, P.S. #1840
Found nail and cap, 3 accessories
- 1978 G.C.R.C. Irish Road - Found re-rod in monument box, 3 accessories
- 1983 G.C.R.C. Irish Road - Found 1/2" re-rod in monument box, 3 accessories
- 1990 L.C.R.C. L 2392, P. 159 by Grant J. Ward, R.L.S. #22445, 4 accessories
- 1993 Survey L3410, P. 635 by James E. Kauas, R.L.S. #33138, 4 accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" re-rod in monument box, and 1 accessory from 1928 G.C.R.C. Irish Road plans. Distance from C-5 to C-4 by stationing of 2,633.4 feet. 1978, 2 accessories (S60°E, 92.6 nail and tag in power pole, S45°W, accessories (S60°E, 92.6 nail and tag in power pole, S45°W, 72.30 nail and tag in power pole. 1983, 3 accessories (NE 81.44' top center of fire hydrant, SE 92.08' nail and cap in telephone pole, SW 71.77' nail and cap in power pole), 1987, 2 accessories (S40°E, 92.78 tag SE face of power pole, S55°E, 72.45 tag SW face of power pole). 1990 and 1993 some witnesses, 3 accessories (N50°W, 64.71' spk and disc #22445, NE face utility pole, S55°E, 92.75', nail and disc, S.W. face utility pole, S55°W, 72.43, nail and disc, SE face utility pole.

During my field work I measured between C-5 and C-4, 2632.53', 1928 G.C.R.C. 2633.4, 1993 survey 2632.76 and between C-5 and D-5 2496.71', 1978 G.C.R.C. 2496.62 and 1993 survey 2496.79'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- N45°E, 81.44 Top Center of Fire Hydrant
- S55°E, 92.84 Found Nail/disc Southwest Face Utility Pole
- S55°W, 72.75 Found Nail/disc Southeast Face Utility Pole
- N50°W, 64.71 Found Nail/disc #22445, Northeast Face Utility Pole

Ratified by Genesee County Peer Group November 24, 1999. I set standard Bernstein monument (3 1/4" d. brass cap stamped "Gene County Remonumentation Corner, 1999" with 30" x 2 3/8" C stainless steel tube over 1/2" re-rod.

Signed by


David J. Kenney

Date

December 27, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYOR, JAN. 28, 1978
REVISED MAY 14, 1978
REVISED JAN., 1997

Surveyor's Michigan License No.



Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep.

Carl [Signature]

Date

11-24-99