

MAR 23 2000

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Michael J. Kenney

SECTION

For corners in

Genesee County	Located In: Davison	Corner Code # G-4
1. Public Land Survey	T 7N R 8E	G-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claim _____		

DEC 28 10 38 AM '99

GENESEE COUNTY REGISTER OF DEEDS

4358, P. 739

Register of Deeds Stamp & File Num 1

I, David J. Kenney, in a field survey on November, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 G.L.O. Joseph Wampler D.S.
- 1929 G.C.R.C. record book for Davison Township, Sheet 1, #4, Iron, 4 accessories
- 1975 L.C.R.C., L 1906, P. 400 by Ronald W. Keller
Found monument box, 3 accessories
- 1979 L.C.R.C., L 2057, P. 400 by Myron L. Petrie, Found 1/2" rod in 1/2" pipe, 6" below conc. in monument box, 4 accessories
- 1992 L.C.R.C., L 2481, P. 629, by Paul N. Brown, set P.K. and tag #20709 from previous survey monumentation due to re-surfacing of M-15, 4 accessories
- 1997 Flint Surveying Section Corner Card, Found P.K. and brass tag, 4 accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4 Section Corner, Section 9 & 10, T7N-R8E, Davison Township

Found P.K. nail with brass tag 1.4' west of centerline of M-15 and 31' +/- north of centerline of South Street, and 1 accessory from L.C.R.C., L1906, P. 400, (power pole S30°E, 62.50'), 2 accessories from L.C.R.C., L 2057, P. 961 (S20°W, 62.32' power pole, S40°E, 62.27 power pole and telephone pole); L.C.R.C., L 2481, P. 629, 1 accessory (S24°W, 62.83' set tag #20709 in NW face of power pole); accessories (N20°E, 73.66, set nail and tag "KRC" in power pole, S85°E, 26.18', set nail and tag "KRC" in power pole, S23°W, 62.82', found nail and tag #20709 in power pole and S80°W, 26.27', found nail and tag "MSHD" in power pole).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 Section Corner, Section 9,10, T7N-R8E, Davison Township

N20°E, 73.66', Found Nail and Tag "KRC" in power pole
S85°E, 26.18', Found Nail and Tag "KRC" in power pole
S23°W, 62.82', Found Nail and Tag #20709 in power pole
S80°W, 26.27', Found Nail and Tag "MSHD" in power pole

Ratified by Genesee County Peer Group November 17, 1999. 1 set standard Bernstein monument (3 1/4" d. brass cap stamped "Genesee County Remonumentation Corner, 1999" with 30" x 2 3/8" O. stainless steel tube over P.K. nail with brass tag.

Signed by


David J. Kenney

Date

December 27, 1999

Surveyor's Michigan License No.

39083



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYOR, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. *Carl Carlson*

Date 11-17-99