

REMONUMENTATION CORNER UNDER ACT 345, MICHIGAN PUBLIC ACTS OF 1990

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GENESEEE

(County)

Located In

Danison

Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|-----------|------------|
| 1. Public Land Survey | T | <u>7N</u> | R | <u>8E</u> | <u>H-3</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DONALD G. RICHARDS, in a field survey on December 3, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Joseph Wampler and field party
fall 1821
S 71 W 16 a Beech 18 in dmtr
N 50 E 22 a Beech 12 in dmtr
(see reverse side for additional information)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found rered in Monument Box

SURVEY &
REMONUMENTATION

MAR 16 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Bernsten monument SS-A5BR-30 stamped "Genesee County Remonumentation Corner" over rered in Monument Box
S 40 W 43.81' nail/GCWT* in SE face 15" Maple
NORTH 44.89' nail/GCWT in S face power pole
N 50 E 60.45' nail/GCWT in NW face 30" Maple
SOUTH 45.24' nail/GCWT in N face power pole
WEST 2638.72' section corner G-3, T7N-R8E
EAST 2633.06' section corner I-3, T7N-R8E
(* Genesee County Witness Tag)

RECORDED
REGISTERED
Dec 27 9 11 AM '93
GENESEEE COUNTY
FLINT MICHIGAN
77975
FILED & RECORDED
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

