

**1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Melvin S. McLee

For corners in

Genesee County

Located In: Davison Corner Code # I-5

Dec 28 10 39 AM '99

- | | | | | | |
|--------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey | T | 7N | R | 8E | I-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Section | S | T | R | | |
| | S | T | R | | |
- SECTION**
4. Lot No. _____ Recorded Plat _____
5. Private Claim _____

**GENESEE COUNTY
REGISTER OF DEEDS**

L. 4358, P. 748

Register of Deeds Stamp & File Num

I, David J. Kenney, in a field survey on November, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 G.L.O. Joseph Wampler D.S. - Set post
- 1971 LCRC, L 1837, P. 197 by A.F. Miller - Found 1" pipe, 2 accessories
- 1973 LCRC, L 1863, P. 101 by Karal Piotrowski - Found 1" pipe, set monument box, 3 accessories
- 1976 GCRC, Oak Road plans - Found 1" pipe, set monument box, 4 accessories
- 1984 LCRC, L 2062, P. 348 by Myron Petrie - Found 1" pin in monument box, 5 accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-5 Section Corner, Sections 10,11,14,15, T7N-R8E, Davison Township.

Found 1" pin in monument box and 2 accessories from 1971, LCRC, L 1837, P. 197 (NW corner house S70°E 67.45' and center of sanitary manhole, N35°W, 50.87'), 2 accessories from 1976 GCRC, Oak Road plans, (N35°W, 50.87', center of sanitary manhole, S70°E, 67.45' NW corner house #1003), 3 accessories from 1984, LCRC, L 2062, P. 348, (N75°E, 35.92', Tree, N23°W, 49.83' chiseled '+' on southerly rim of sanitary manhole, S55°E, 67.51' NW corner of foundation of house #1003).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5 Section Corner, Sections 10,11,14,15, T7N-R8E, Davison Township.

N35°W 50.84' Found chiseled 'T' on South edge of sanitary manhole.
S70°E 67.45' Northwest corner of house foundation #1003.
S60°W 43.53' Found P.K. and tag #23828 in fence post.
N50°W 40.75' Found P.K. and tag #23828 in fence post.
East 50.00' Found concrete monument.

Ratified by Genesee County Peer Group November 24, 1999.
I set the standard Bernstein monument (3 1/4" d. brass cap stamped "Genesee County Remonumentation Corner, 1999" with 30" x 2 3/8" O.D. stainless steel tube over 1" pin in monument box.

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. *Carl Carlson*
Date 11-24-99

Signed by

David J. Kenney

Date December 27, 1999

Surveyor's Michigan License No.

