

SURVEY & REMONUMENTATION

MAR 23 2000

**1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Melinda Mc Lee

For corners in **SECTION**

Genesee County Located In: Davison Corner Code # J-5

1. Public Land Survey	T	7N	R	8E	J-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

DEC 28 10 39 AM '99

GENESEE COUNTY REGISTER OF DEEDS

L. 4358, P. 747

Register of Deeds Stamp & File Num

4. Lot No. _____ Recorded Plat _____
5. Private Claim _____

I, David J. Kenney, in a field survey on November, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- 1822 G.L.O. Joseph Wampler D.S. - Set post
G.C.R.C. Witness book, P. 6 - Found 3/4" iron, 4 accessories
- 1977 L.C.R.C. L 2021, P. 682 by Kenneth D. Dunton - Found 3/4" pipe, 4 accessories
- 1995 L.C.R.C. L 2586, P. 709, Survey L 2586, P. 710 by Brad F. Thompson, LS #23828 - Found 3/4" pipe, 4 accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5 Section Corner, Sections 11, 14, T7N-R8E, Davison Township

Found 3/4" iron pipe, 1.0' below surface of gravel road, and 1 accessory from GCRC witness book, (West 31.5' fence post). Note that the 12" wood fence post is leaning westerly due to side slope of the ditch at base of fence post. From the LCRC, L2021, P. 682, 4 accessories (N45°W, 72.72 RLS 11192 tag power pole, N80°W 31.90' MSHD tag wood fence post, S60°W 84.24' NE corner house #1014, and South 204.85' 1/2" re-rod in monument box at centerline Lapeer Road and N-S 1/4 line intersection). 4 accessories from LCRC L 2586, P. 709 and survey L 2586, P. 710 (N25°E 49.91' Found P.K. nail west side telephone pole, S65°W 83.96 to NE corner of house #1014, N80°W, 32.66' Found nail with MDOT tag south side fence post, N35°W, 76.03' Found concrete nail with tag #11192 NE side power pole).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 Section Corner, Sections 11,14, T7N-R8E, Davison Township

- N80°W, 32.66' Found MSHD tag in south face wood fence post
- S60°W, 83.95' Northeast corner of House foundation #1014
- N25°E, 50.33' Found P.K. in northwest face telephone pole
- N35°W 76.20' Found P.K. in easterly face of power pole
- South 203.30' Top center of monument box in centerline of Lapeer Road

Ratified by Genesee County Peer Group November 24, 1999. I set the standard Bernstein monument (3 1/4" d. brass cap stamped "Genesee County Remonumentation Corner, 1999" with 30" x 2 3/8" O.D. stainless steel tube over 3/4" iron pipe.

Ratified by Peer Group in accordance with P.A. 345, 1990

Co. Rep. *Carl Carlson*
Date 11-24-99

Signed by

David J. Kenney
DAVID J. KENNEY
LAND SURVEYOR
No. 39083

Date December 27, 1999

Surveyor's Michigan License No. 39083