

**SURVEY &
REMONUMENTATION**

**APR 29 1996
COMMISSION**

DEED LIBER 2601 PAGE 271

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>DATE/SOURCE</u>	<u>MONUMENT/ACCESSORY DESCRIPTION</u>	<u>FR. COR.</u>		<u>DISTANCE</u>	<u>RECOVERY DISTANCE</u>
1822/GLO Notes	Deputy Surveyor Horatio Ball	I-5	I-4	40.00 ch (2640')	2632.72' (39.89 ch)
	Set post 40.00 chains North of I-5	I-4	I-3	40.00 ch (2640')	2642.39' (40.04')
	Lynn 4" N70E 3 links Maple 8" S85W 10 links				
1890/GCSR Notes	Moses Middleton, C.S. Stone	I-5	I-4	39.90 ch (2633.4')	2632.72' (39.89 ch)
	Beech 12" S48W 68 links	I-4	I-3	40.12 ch (2647.82')	2642.39' (40.04 ch)
1974/Survey & Field Notes	Rowe Engineering, Inc Odd H. Johnsrud PS 18434, L 1893 pgs 303-304	H-3	H-4	2627.80	2628.01'
	Fnd remains of anchor post/set iron in ctr	H-4	I-4	2648.60'*	2667.06'
		I-3	I-4	2642.41'	2642.39'
		H-3	I-3	2622.55'*	2662.60'
	[*Incorrect Measurements]	Angle H-3, H-4, I-4		89°58'15"	89°58'15"