

**SURVEY & REMONUMENTATION COMMISSION**  
**APR 07 1995**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

(REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. OF 1990)

For corners in  
**GENESEE**  
 (County)

Located In:

Corner Code A-3

RECORDED

GENESEE COUNTY  
 DEED LIBER **2528** PAGE **806**

14716

9.00 Filed & Red.  
 Register of Deeds Stamp & File Number

- 1. Public Land Survey T 8N R 6E \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RICHARD H. KRAFT, in a field survey on NOVEMBER 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1822 GLO, HORATIO BALL. SET POST 1993 CERTIFIED SURVEY, PAUL BROWN FOUND "T" IRON IN MONUMENT BOX. LIST 3 ACCESSORIES
- 1878 WILLIAM B. SEARS, FOUND STAKE AND STONE. LOT 2 ACCESSORIES
- GCRC, FOUND STONE AND CROCK LOT 3 ACCESSORIES, NO DATE.
- 1954 GCRC, CORNER NOT IDENTIFIED LOT 2 ACCESSORIES

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1993 GENESEE COUNTY REMON. PROGRAM RECOVERED "T" IRON IN MONUMENT BOX 3 ACCESSORIES FORM 1993 1 ACCESSORY FROM 1954
- I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGED. THE RECOVERED ACCESSORIES SHOW IT IS IN THE SAME POSITION. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY GENESEE COUNTY PEER REVIEW GROUP  
 DECEMBER 7, 1993.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
**ACCESSORIES:**

- N45°W, 35.86' SET NAIL /G.C. REMON. TAG IN PAVEMENT
  - N40°E, 53.12' FOUND NAIL AND TAGE IN GUY POLE
  - SOUTH, 32.55' FOUND MON. BOX; NE COR. SECTION 13 T8N; R5E
  - S40°W, 90.12' FOUND NAIL AND TAG IN LIGHT POLE
- I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONUMENTATION CORNER, 1993", WITH 2 3/8" O.D. STAINLESS STEEL TUBE) OVER "T" IRON IN MONUMENT BOX.

Signed by

*Richard H. Kraft*

Date

Nov. 19, 1993

Surveyor's Michigan License No. 10067