

DEED LIBER 2601 PAGE 934
 1995 Re-monumentation Program
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

GENESEE COUNTY
 REGISTERED DEEDS

JUN 11 2 10 PM '96

RECORDS

RECORDED

or corners in

Genesee (County) Located In: Corner Code #

- 1. Public Land Survey T 8N R 6E A-4
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

SURVEY &
 REMONUMENTATION

2356

Register of Deeds Stamp & File Number

APR 29 1996

- 4. Lot No. , Recorded Plat COMMISSION
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Kevin B. Cleaver, P.S., in a field survey on September 15, 1995

to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- October 30, 1962 Recorded plat of "Stanley Acres" plat monuments
- July 30, 1964 Recorded plat of "Stanley Acres No. 1" plat monuments

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" solid steel rod in monument box
 This monument fits the recorded plats listed in section A.

The monument found was ratified by the Genesee County Peer Review Committee on November 1, 1995, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Berntsen monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1995, #29242 over a 1" solid steel rod in monument box.

- N 40° W, 73.59' - Found PK nail and washer in Southeast face of power pole
- S 56° W, 58.93' - Found concrete monument
- East, 49.78' - Found chiseled 'X' in top of right-of-way marker
- South, 31.63' - Found M-4, T8N-R5E, re-monumentation pipe and disk #33134, 0.75 E of A-4 to A-5
- South, 2621.06' - Corner A-5, T8N-R6E, 1995 GCRC-monument #29242

Signed by Kevin Banfield Cleaver Date Jun 9, 1996
 Surveyor's Michigan License No. 29242 By: Kevin Banfield Cleaver, P.S.
 Its Field Manager

