

Notified by Peer Group In  
conformance with P.A. 345, 1990

DEED LIBER 2601 PAGE 933

Co. Rep. Carl Larkin  
Date Jan 9, 1996

1995 Remonumentation Program  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

GENESEE COUNTY  
REGISTER OF DEEDS

JAN 11 2 10 PM '96

RECORDED

RECORDED  
P. B. P. M. A.

For corners in

Genesee <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>6E</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____	<b>COMMISSION</b>	
5. Private Claims _____		

**SURVEY &  
REMONUMENTATION**

2355

APR 29 1996

Register of Deeds Stamp & File Number

*900  
filed  
me*

I, Kevin B. Cleaver, P.S., in a field survey on September 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1821, GLO Set post and two (2) accessories
- 1915, GCRC Route and course description Project No. 8165 - C-9
- October 30, 1962 Recorded plat of "Stanley Acres", plat monuments
- July 30, 1964 Recorded plat of "Stanley Acres No. 1", plat monuments
- 1979 Certified survey, Liber 2051, Page 658 - RRS in pavement, three (3) accessories
- 1980 Certified survey, Liber 2075, Page 993 - RRS in pavement, same three (3) accessories as 1979, (Liber 2051, Page 658)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" re-rod in monument box, distance between A-5 to B-5 closely fits 1915 GCRC description, also fits found monumentation of the 1962 plat of "Stanley Acres" and found monumentation of the 1964 plat of "Stanley Acres No. 1". This monumentation also fits the 1979 and 1980 accessory (center of monumentation box M-5, T8N-R5E to south recorded at 38.82')

The monument found was ratified by the Genesee County Peer Review Committee on November 1, 1995, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Berntsen monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1995, #29242 in concrete over a 1/2" re-rod in monument box.

- S 45° E, 63.82' - Found nail/flagging in west face of power pole
- N 43° E, 69.82' - Found spike and cap #11192 in northwest face of power pole
- S 79° W, 44.16' - Found PK nail/flagging in North face of power pole
- N 36° W, 73.71' - Found nail/white square plastic tag in northeast face of power pole

Signed by Kevin Benfield Cleaver By: Kevin Benfield Cleaver, P.S. Date Jan 9, 1996  
Surveyor's Michigan License No. 29242 Its Field Manager No. 29242

