REMONUMENTATION APR 07 1995

LAND CONNER RECORDATION VERTIFICATE,	
Filing Requirement of Act 74, Mich. P.A. 1970	2 47
rlling Requirement of Act /4, Mich. P.A. 1970	£ 41

2	47		


Fau same as to	· SVIII	rang negatement of Act 14, with P.A. 1910			
For corners in	COMMIS	(REMONUMENTATION	CORNER UNDER P.A.	345 MICHIGAN P.A.	OF 1990)
GENESEE (County)	<u> </u>	Located In:	Corner Code a##	DEED 2528 PAGE	807
Public Land Sur	vey	T8N R 6E	B-3	LIDER A C A IS KNOW	


	·	TR TR	- Company of the control of the cont	14747	
_		T R			•
2.	Property Controlling in Section	S T R S T R		and Filed + Bud	

Register of Deeds Stamp & File Number 3. Miscellaneous Property in Sec.

I, RICAHRD H. KRAFT , in a field survey on NOVEMBER 18 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:





1878 WILLIAM B. SEARS, SET STONE. LIST 1 ACCESSORY

\_\_\_\_ , Recorded Plat

4. Lot No. 5. Private Claims ....

- 1954 GCRC - FOUND PIPE AND STAKE LIST 5 ACCESSORIES
- WITH RAILROAD SPIKE. LIST 3 ACCESSORIES.
- 1993 CERTIFIED SURVEY. FOUND PIPE IN MONUMENT BOX. LIST 4 ACCESSORIES
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
  - 1993 GENESEE COUNTY REMON. PROGRAM RECOVERED PIPE IN MONUMENT BOX 4 ACCESSORIES FORM 1993

I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGED. THE RECOVERED ACCESSORIES SOW IT IS IN THE SAME POSITION. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER. APPROVED BY GENESEE COUNTY PEER REVIEW GROUP, DEC. 7, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCESSORIES:

N25°E, 75.77' - SET NAIL/G.C. REMON.TAG

IN 30" MAPLE

N45°E, 68.83' - FOUND MONUMENT S30°E, 26.31' - FOUND RE-ROD AT EDGE OF

SHOULDER

SOUTH, 60.98" - FOUND NAIL AND TAGEIN 10"

THORNAPPLE

I SET THE STANDARD BERNSTEN MONUMENT ( 3 1/4" D. BRASS CAP STAMPED "GENESEE COUNTY REMONMENTATION CORNER; 1993" WITH 2 3/8" O.D. STAINLESS STEEL TUBE) OVER PIPE IN MONUMENT

Surveyor's Michigan License No.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 23, 1975