

SURVEY & REMONUMENTATION

APR 29 1996

Notified by Peer Group in accordance with P.A. 345, 1990

By Rep. Kevin Banfield Cleaver
 Date Jan 9, 1996

COMMISSION
 1995 Remonumentation Program
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

DEED LIBER 2601 PAGE 931
 REGISTERED OFFICE
 GENESSEE COUNTY
 JAN 11 2 10 PM '96
 REGISTERED OFFICE
 2353
 Register of Deeds Stamp & File Number

For corners in

<u>Genesee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>6E</u>	<u>C-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kevin B. Cleaver, P.S., in a field survey on September 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--------------|---|
| 1821±, GLO | Set post with two (2) accessories |
| 1915, GCRC | Project A-8177, linear distance C-5 to C-4 |
| 1954, CP Co. | Iron with three (3) accessories |
| 1974 | Certified survey, Liber 1901, Page 581, set 1/2" re-rod from plat with three (3) accessories |
| 1976 | Certified survey, Liber 1935, Page 151, 5/8" re-rod with two (2) accessories from 1974, one (1) new accessory |
| 1980 | Certified survey, Liber 2116, Page 804-806, 5/8" re-rod with three (3) accessories from 1976 |
| 1992 | Certified survey, Liber 2478, Page 764-765, 1/2" re-rod in monument box 0.8' west of center line of pavement with one (1) accessory from 1980 and three (3) new accessories |
| 1993, LCRC | Liber 2487, Page 260-261, found iron rod in monument box, as recorded in Liber 1901, Page 581, four (4) new accessories |
| 1993 | Certified survey, Liber 2941, Page 259-260, found 1/2" re-rod in monument box with three previous accessories and one (1) new accessory |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" re-rod in monument box. Found three (3) accessories from the 1974 survey, Liber 1901, Page 581; found one (1) new accessory from the 1976 survey, Liber 1935, Page 151; found three (3) new accessories from the 1992 survey, Liber 2478, Pages 764-765; found four (4) new accessories from 1993, LCRC, Liber 2487, Pages 260-261; found one (1) new accessory from the 1993 survey, Liber 2491, Pages 259-260.

The monument found was ratified by the Genesee County Peer Review Committee on November 1, 1995, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30 with 3 1/4" brass cap stamped Genesee County Re-monumentation Corner 1995, #29242 over a 1/2" re-rod in a monument box 1.0' west of center line of asphalt.

- | | | |
|----------|--------|--|
| N 40° E, | 57.12' | - Found spike/tag #20709 in southeast face of 9" Elm Tree |
| S 43° E, | 64.50' | - Found nail/tag #20709 in northeast face of 6" Elm Tree |
| S 50° W, | 18.32' | - Found southeast corner north headwall |
| N 76° W, | 46.69' | - Found 60d spike/disc #22445 in northeast face of 8" Cedar Tree |
| East, | 30.46' | - Found PK nail/tag in west face of power pole |

Signed by Kevin Banfield Cleaver Date Jan 9, 1996
 Surveyor's Michigan License No. 29242 By: Kevin Banfield Cleaver, P.S.
 Its Field Manager No. 29242

