

SURVEY & REMONUMENTATION
APR 07 1995

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970,
(REMONUMENTATION CORNER UNDER P.A. 345, MICHIGAN P.A. OF 1990)

For corners in
GENESEE
(County)

Located In: Corner Code #/H

DEED LIBER **2528** PAGE **808**

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T <u>8N</u> R <u>6E</u> | D-3 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

14743

9.00 Filed & Recd
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

RICHARD H. KRAFT, in a field survey on **NOVEMBER 18,** 19**93**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| 1822 GLO HORATIO BALL, SET POST | 1974 CARL CARLSON, FOUND 3/4" IRON BAR LIST 3 ACCESSORIES |
| 1886 J.W. PETTIE, FOUND STONE AND SET IRON STAKE, LIST 2 ACCESSORIES | 1974 K. PIOTROWSKI, FOUND MONUMENT BOX LIST 3 ACCESSORIES |
| 1954 GCRC - FOUND IRON PIN LIST 7 ACCESSORIES | 1989 CERTIFIED SURVEY, PAUL BROWN LIST 4 ACCESSORIES |
| | 1992 CERTIFIED SURVEY, PAUL BROWN, FOUND 3/4" ROD IN MON. BOX. LIST 4 ACCESSORIES |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 GENESEE COUNTY REMON. PROGRAM RECOVERED 1" IRON ROD IN MON. BOX 3 ACCESSORIES FORM CERTIFIED SURVEY, 1992	I CONCLUDE THAT THE CORNER HAS LONG BEEN PERPETUATED AND DOESN'T SEEM TO HAVE CHANGED. THE RECOVERED ACCESSORIES SHOW IT IS IN THE SAME POSITION. I ACCEPT IT AS A FAITHFUL AND CAREFUL RESTORATION OF THE POSITION OF THE ORIGINAL CORNER.
--	---

APPROVED BY GENESEE COUNTY PEER REVIEW GROUP,
 DECEMBER 7, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ACCESSORIES: NORTH, 51.90' FOUND NAIL AND TAG IN POWER POLE SOUTH, 44.40' FOUND NAIL AND TAG IN POWER POLE S10°W, 44.40' FOUND NAIL AND TAG IN 10" OAK S45°W, 57.22' SET NAIL/G.C. REMON. TAG IN 20" TWIN ELM N50°E, 76.95' SET NAIL/G.C. REMON. TAG IN 4" CEDAR	I SET THE STANDARD BERNSTEN MONUMENT (3 1/4" D. BRASS CAP STAMPED - "GENESEE COUNTY REMONUMENTATION CORNER. 1993" WITH 2 3/8" O.D. STAINLESS STEEL TUBE) OVER IRON ROD IN MONUMENT BOX.
---	---

Signed by *Richard H. Kraft*
 Surveyor's Michigan License No. 10064

Date Nov 19, 1993

E