

**SURVEY &
REMONUMENTATION**

Ratified by Peer Group in
conformance with P.A. 845, 1990

APR 29 1996

Co. Rep. Carl Carlson
Date Jan 9, 1996

COMMISSION
1995 Remonumentation Program
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEAD
CLIPPER 2601 PAGE 926

For corners in

<u>Genesee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>6E</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

GENESEE COUNTY
REGISTER OF DEEDS
 JAN 11 2 09 PM 1996
 REGISTERED
 F. RECORDS
 200
 900
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kevin B. Cleaver, P.S., in a field survey on September 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---------------------|--|
| 1821± | Set 1/4 post, with two (2) accessories |
| 1915, GCRC | Project A-8164, linear distance E-5 to F-5 to G-5 |
| Date(?) GEI records | 1 1/4" X 18" gas pipe, with five (5) accessories |
| 1954 | Record plat of "Funsch Gardens" |
| 1954(?) | MSHD, Route I-75/US 23 control maps |
| 1964, GEI records | Monument box-MSHD, with one (1) accessory from 1954 and four (4) new accessories |
| 1986 | Certified survey, L 2292, P 653 and 654, found 3" disc in concrete with four (4) new accessories |
| 1991, LCRC | L 2417, P 257 and 258, found "+" in brass disc, with four (4) new accessories |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" diameter brass disc in concrete pavement; found distance E-5 to F-5 and F-5 to G-5 from 1915 GCRC project; found plat monumentation from the recorded plat of "Funsch Gardens" 1954; found distance F-5 to E-5, 1954 MSHD survey; found one (1) accessory from 1964 Gould Engineering, Inc. (GEI), records; found brass disc and four (4) accessories from 1986 certified survey; found brass disc and four (4) accessories from 1991, LCRC.

The monument found was ratified by the Genesee County Peer Review Committee on November 1, 1995, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 3" diameter brass disc in concrete pavement.

- | | | | |
|----------|--------|---|---|
| N 44° E, | 33.90' | - | Found chiseled 'X' in base of concrete guardrail |
| S 48° E, | 33.93' | - | Found chiseled 'X' in base of concrete guardrail |
| N 72° W, | 61.43' | - | Found nail/tag #22445 in top of wood guardrail post |
| S 56° W, | 57.00' | - | Found northeast corner of concrete support |
| S 64° W, | 61.72' | - | Found nail/tag #22445 in top of wood guardrail post |

Signed by Kevin B. Cleaver Date Jan 9, 1996
 Surveyor's Michigan License No. 29242 Its Field Manager

