

REMONUMENTATION

MAY 20 1987

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Genesee <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T 8N R 6E	G-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED
Dec 30 11 37 AM '96
REGISTERED

42558

900

FILED & RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kevin B. Cleaver, P.S. a field survey on November 1, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1821, GLO Set post
 - Oct. 22, 1946 recorded plat "Brent Creek Gardens" L-20, P-35
 - Date ? GEI records
 - Aug. 31, 1973 Certified survey L-1868, P-728
 - Oct. 18, 1973 LCRC, L-1875, P-602
 - Nov. 12, 1974 Certified survey, L-1903, P-245
 - Oct. 26, 1979 Certified survey, L-2072, P-335 and 336
 - Jan. 27, 1987 LCRC, PS#2351
 - June 8, 1987 Certified survey, L-2292, P-653 and 654
 - Jan. 7, 1996 LCRC, L-2417, P-258

Ratified by Peer Group in accordance with P.A. 345, 1990
Co. Rep. Carl Carlson
Date 10-30-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 3/4" iron in monument box with a 1/2" rod 0.07' North; found one (1) accessory from GEI records; found three (3) accessories from Aug. 31, 1973 survey; found three (3) accessories from Nov. 12, 1974 survey; found three (3) accessories from Oct. 26, 1979 survey; found three (3) accessories from Jan. 27, 1987 LCRC; found three (3) accessories from June 8, 1987 survey, found three (3) accessories from Jan. 7, 1996 LCRC.

The monument found was ratified by the Genesee County Peer Review Committee on October 30, 1996, as the accepted corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set the standard Bernsten monument SS-A-5-BR-30, with 3/4" brass cap stamped Genesee County Remonumentation Corner 1996, #29242 over 3/4" iron in monument box.

- S 87° E 64.18' Found nail/tag in South face of power pole
- S 84° E 53.62' Found nail/tag #22445 in North face of 24" ash
- S 89° W 36.27' Found nail/tag #22445 in North face of 12" elm
- South 2659.20' Southeast corner Section 9, T8N R6E

Signed by Kevin Banfield Cleaver Date Nov 1, 1996
Kevin Banfield Cleaver, P.S., Field No. 29242
Surveyor's Michigan License No. 29242

