

REMONUMENTATION

MAY 20 1997

MASTER LIBER 3436 PAGE 803

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
RECORDED
DEC 30 11 37 AM '96

For corners in

Genesee <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>6E</u>	<u>H-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

83526

Register of Deeds Stamp & File Number

9⁰⁰

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kevin B. Cleaver, P.S. in a field survey on November 1, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1821, GLO Set post with two (2) accessories
- Date ? GEI records, 3/4" gas pipe, with four (4) accessories
- Oct. 18, 1976 Certified survey, Liber 1950, Page 666, found pinch bar with three (3) accessories
- Jan. 19, 1977 LCRC, Liber 1977, Page 807, found pinch bar with three (3) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pinch pipe in monument box; found one (1) accessory from GEI records; found pinch bar and three (3) accessories from Oct. 18, 1976 survey; found pinch bar and three (3) accessories from Jan. 19, 1977 LCRC.

The monument found was ratified by the Genesee County Peer Review Committee on October 30, 1996, as the accepted corner.

Ratified by Peer Com.
accordance with P.A. 345
Co. Rep. Kevin B. Cleaver
Date 10-30-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set the standard Bernsten monument SS-A-5-BR-30, with 3/4" brass cap stamped Genesee County Remonumentation Corner 1996, #29242 over 3/4" pinch pipe in monument box.

- North 36.46' Set remon tag in the East face of power pole
- N 45° W 35.88' Set remon tag on landscape timber at East line of drive for house #3272
- N 40° E 43.42' Set remon tag in the Northwest face of 10" maple
- S 10° E 70.53' Set remon tag in the Northeast face of 10" twin maple

Signed by Kevin Banfield Cleaver
Kevin Banfield Cleaver, P.S. Its. Field Manager
Surveyor's Michigan License No. 29242

