

MAY 20 1997

1996 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Genesee

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>6E</u>	<u>I-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

3436

RECORDED
REGISTERED
DEC 30 11 37 AM '96
FILED

900

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kevin B. Cleaver P.S., a field survey on November 22, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1821, GLO Set post, with two (2) accessories
 - Date ? GEI records; found 1" rod in asphalt with two (2) accessories
 - 1964 GEI records, iron with four (4) accessories
 - Jan. 10, 1972 LCRC 1" iron rod with three (3) accessories
 - Oct. 26, 1972 LCRC fnd iron pin with three (3) accessories
 - May 4, 1979 Survey, L-2045, P-546 and 547, found 1" iron pin with four (4) accessories
 - June 5, 1979 Survey, L-2057, P-442, 443, and 444, fnd 1" iron pin with four (4) accessories
 - March 3, 1989 Survey, L-2357, P-283, fnd 3/4" round iron pin with four (4) accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1" rod in pavement; found two (2) accessories from Gould Engineering, Inc. records; found two (2) accessories from LCRC; found two (2) accessories from certified survey, L-2045, P-546 and 547; found three (3) accessories from certified survey, L-2057, P-442, 443, and 444; found four (4) accessories from certified survey, L-2357, P-283.

The monument found was ratified by the Genesee County Peer Review Committee on October 30, 1996 as the accepted corner.

Ratified in accordance with Act 74, 1970
Co. Rep. Kevin B. Cleaver
Date 10-30-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set the standard Bernsten monument SS-A-5-BR-30, with 3/4" brass cap stamped Genesee County remonumentation corner 1996, # 29242 in a monument box over the found 1" rod in pavement.

- S 38° E 63.67' Found nail and tag in north face of power pole
- S 40° W 65.09' Found MSHD tag in east face of guy pole
- N 40° W 102.92' Found southeast corner of building
- N 45° W 62.79' Found PK nail/disk in southeast face of power pole
- N 45° E 55.36' Found southwest face of 8" round steel sign post

Signed by Kevin Banfield Cleaver Date Nov 22, 1996
Kevin Banfield Cleaver, P.S., Its Field Manager
Surveyor's Michigan License No. 29242

